

August 17, 2005

Mrs. Diana Whitney
State of Utah
Division of Oil, Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Application for Permit to Drill—Dominion Exploration & Production, Inc.
AP 1-2J, 700' FNL & 700' FEL, NE/4 NE/4, (Lot 1), Sec. 2, T11S, R19E, SLB&M, Uintah County, Utah

Dear Mrs. Whitney:

On behalf of Dominion Exploration & Production, Inc. (Dominion), Buys & Associates, Inc. respectfully submits the enclosed original and one copy of the *Application for Permit to Drill (APD)* for the above referenced state surface / state mineral well. Included with the APD is the following supplemental information:

Exhibit "A" - Survey plats, layouts and photos of the proposed well site;

Exhibit "B" - Proposed location maps with access and utility corridors;

Exhibit "C" - Production site layout;

Exhibit "D" - Drilling Plan;

Exhibit "E" - Surface Use Plan;

Exhibit "F" - Typical BOP and Choke Manifold diagram.

Please accept this letter as Dominion's, written request for confidential treatment of all information contained in and pertaining to this application.

Thank you very much for your timely consideration of this application. Please feel free to contact myself or Carla Christian of Dominion at 405-749-5263 if you have any questions or need additional information.

Sincerely,

Don Hamilton

Don Hamilton
Agent for Dominion

cc: Fluid Mineral Group, BLM—Vernal Field Office
Carla Christian, Dominion
Ken Secrest, Dominion

RECEIVED

AUG 22 2005

DIV. OF OIL, GAS & MINING

ORIGINAL
CONFIDENTIAL

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

| | | | |
|---|---|---|-----------------------------|
| APPLICATION FOR PERMIT TO DRILL | | 5. MINERAL LEASE NO: ML-36213 | 6. SURFACE: State |
| 1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/> | | 7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A | |
| B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> | | 8. UNIT or CA AGREEMENT NAME: N/A | |
| 2. NAME OF OPERATOR: Dominion Exploration & Production, Inc. | | 9. WELL NAME and NUMBER: AP 1-2J | |
| 3. ADDRESS OF OPERATOR: 14000 Quail Sp Pkwy CITY Oklahoma City STATE OK ZIP 73134 | | 10. FIELD AND POOL, OR WILDCAT: Natural Buttes Undesignated | |
| 4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 700' FNL & 700' FEL (Lot 1) AT PROPOSED PRODUCING ZONE: 700' FNL & 700' FEL (Lot 1) | | 11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 2 11 19 S | |
| 14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 13.97 miles southwest of Ouray, Utah | | 12. COUNTY: Uintah | 13. STATE: UTAH |
| 15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 700' | 16. NUMBER OF ACRES IN LEASE: 625.62 | 17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40 | |
| 18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 2,410' | 19. PROPOSED DEPTH: 9,500 | 20. BOND DESCRIPTION: SITLA Blanket 76S 63050 361 | |
| 21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5,429' | 22. APPROXIMATE DATE WORK WILL START: 12/1/2005 | 23. ESTIMATED DURATION: 14 days | |

| 24. PROPOSED CASING AND CEMENTING PROGRAM | | | | | | |
|---|---|-----------------|------------|---------------|---|--------------------|
| SIZE OF HOLE | CASING SIZE, GRADE, AND WEIGHT PER FOOT | | | SETTING DEPTH | CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT | |
| 12-1/4" | 8-5/8" | J-55 ST | 32# | 2,000 | see Drilling Plan | 252/219/100 |
| 7-7/8" | 5-1/2" | Mav 80 L | 17# | 9,500 | see Drilling Plan | 160/435 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

| 25. ATTACHMENTS | |
|---|--|
| VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES: | |
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER <input type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

ORIGINAL
CONFIDENTIAL

| | |
|---|--|
| NAME (PLEASE PRINT) Don Hamilton | TITLE Agent for Dominion Exploration & Production, Inc. |
| SIGNATURE <i>Don Hamilton</i> | DATE 8/17/2005 |

(This space for State use only)

API NUMBER ASSIGNED: **43-047-32041**

APPROVAL:
 Approved by the
 Utah Division of
 Oil, Gas and Mining
 Date: **09-14-05**
 By: *[Signature]*

RECEIVED
AUG 22 2005
DIV. OF OIL, GAS & MINING

T11S, R19E, S.L.B.&M.

DOMINION EXPLR. & PROD., INC.

Well location, AP #1-2J, located as shown in the NE 1/4 NE 1/4 of Section 2, T11S, R19E, S.L.B.&M. Uintah County, Utah.

T10S

T11S

S89°34'W - 2671.02 (G.L.O.)

-N89°15'10"E - 2653.38' (Meas.)

1956 Brass Cap,
0.5' High, Pile
of Stones

1956 Brass Cap,
0.5' High, Pile
of Stones

AP #1-2J

Elev. Ungraded Ground = 5429'

Lot 4

Lot 3

Lot 2

Lot 1

2

N00°01'W - 5141.40 (G.L.O.)

C.C.
5/8" Rebar No
Cap, 0.4' High,
Pile of Stones,
Old Lath

Set Marked
Stone, Scattered
Pile of Stones

S00°21'36"E - 2502.50' (Meas.)

1960 Brass Cap,
1.0' High, Pile
of Stones

S89°59'W - 5274.72 (G.L.O.)

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

(NAD 83)

LATITUDE = 39°53'39.68" (39.894356)

LONGITUDE = 109°45'08.64" (109.752400)

(NAD 27)

LATITUDE = 39°53'39.81" (39.894392)

LONGITUDE = 109°45'06.14" (109.751706)

LEGEND:


└─┘ = 90° SYMBOL

● = PROPOSED WELL HEAD.

▲ = SECTION CORNERS LOCATED.

BASIS OF ELEVATION

SPOT ELEVATION AT THE SOUTHWEST CORNER OF SECTION 20, T10S, R19E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN. NW QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5251 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME, OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF

John A. Hays
REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

| | | |
|-------------------------|---------------------------------------|-------------------------|
| SCALE 1" = 1000' | DATE SURVEYED: 05-17-05 | DATE DRAWN: 05-31-05 |
| PARTY B.B. J.M. L.K. | REFERENCES G.L.O. PLAT | |
| WEATHER WARM | FILE DOMINION EXPLR. & PROD., INC. | |

DRILLING PLAN

APPROVAL OF OPERATIONS

Attachment for Permit to Drill

Name of Operator: Dominion Exploration & Production
Address: 14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134
Well Location: AP 1-2J
700' FNL & 700' FEL
Section 2-11S-19E
Uintah County, UT

1. GEOLOGIC SURFACE FORMATION Uintah

2. ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS

| <u>Formation</u> | <u>Depth</u> |
|-------------------|--------------|
| Wasatch Tongue | 3,825' |
| Uteland Limestone | 4,155' |
| Wasatch | 4,295' |
| Chapita Wells | 5,195' |
| Uteland Buttes | 6,325' |
| Mesaverde | 7,170' |

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS

| <u>Formation</u> | <u>Depth</u> | <u>Type</u> |
|-------------------|--------------|-------------|
| Wasatch Tongue | 3,825' | Oil |
| Uteland Limestone | 4,155' | Oil |
| Wasatch | 4,295' | Gas |
| Chapita Wells | 5,195' | Gas |
| Uteland Buttes | 6,325' | Gas |
| Mesaverde | 7,170' | Gas |

4. PROPOSED CASING PROGRAM

All casing used to drill this well will be new casing.

| <u>Type</u> | <u>Size</u> | <u>Weight</u> | <u>Grade</u> | <u>Conn.</u> | <u>Top</u> | <u>Bottom</u> | <u>Hole</u> |
|-------------|-------------|---------------|--------------|--------------|------------|---------------|-------------|
| Surface | 8-5/8" | 32.0 ppf | J-55 | STC | 0' | 2,000' | 12-1/4" |
| Production | 5-1/2" | 17.0 ppf | MAV-80 | LTC | 0' | 9,500' | 7-7/8" |

Note: The drilled depth of the surface hole and the setting depth of the surface casing may vary from 1,700' to 2,000'. Should a lost circulation zone be encountered while drilling, casing will be set approximately 300' below the lost circulation zone. If no lost circulation zone is encountered, casing to be set at 2,000'±.

CONFIDENTIAL

DRILLING PLAN

APPROVAL OF OPERATIONS

5. OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL

Surface hole: No BOPE will be utilized. Air foam mist, rotating head and diverter system will be utilized.

Production hole: Prior to drilling out the surface casing shoe, 3,000 psi or greater BOP equipment will be installed. The pipe rams will be operated at least once per day from intermediate casing to total depth. The blind rams will be tested once per day from intermediate casing to total depth if operations permit.

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. As denoted there will be two valves and one check valve on the kill line, two valves on the choke line, and two adjustable chokes on the manifold system. The BOP "stack" will consist of two BOP rams (1 pipe, 1 blind) and one annular type preventer, all rated to a minimum of 3,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling below the intermediate casing shoe. All test pressures will be maintained for fifteen (15) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items.

| | | |
|----|---|-----------|
| 1. | Annular BOP | 1,500 psi |
| 2. | Ram type BOP | 3,000 psi |
| 3. | Kill line valves | 3,000 psi |
| 4. | Choke line valves and choke manifold valves | 3,000 psi |
| 5. | Chokes | 3,000 psi |
| 6. | Casing, casinghead & weld | 1,500 psi |
| 7. | Upper kelly cock and safety valve | 3,000 psi |
| 8. | Dart valve | 3,000 psi |

6. MUD SYSTEMS

- An air or an air/mist system may be used to drill the surface hole until water influx becomes too great.
- KCL mud system will be used to drill well.

| <u>Depths</u> | <u>Mud Weight (ppg)</u> | <u>Mud System</u> |
|-----------------|-------------------------|---|
| 0' – 2,000' | 8.4 | Air foam mist, rotating head and diverter |
| 2,000' – 9,500' | 8.6 | Fresh water/2% KCL/KCL mud system |

7. BLOOIE LINE

- An automatic igniter will not be installed on blooie line. The blooie will have a constant ignition source.
- A "target tee" connection will be installed on blooie line for 90° change of directions for abrasion resistance.
- "Target tee" connections will be a minimum of 50' from wellhead.
- The blooie line discharge will be a minimum of 100' from the wellhead.

8. AUXILIARY EQUIPMENT TO BE USED

- a. Kelly cock.
- b. Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string.

9. TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED

- A drillstem test in the Wasatch Tongue is possible.
- One electric line wire-log will be run from total depth to surface casing.
- The gamma ray will be left on to record from total depth to surface casing.
- Other log curves (resistivities, porosity, and caliper) will record from total depth to surface casing.
- A dipmeter, percussion cores, or rotary cores may be run over selected intervals.

10. ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED

- Expected BHP 1,500–2,000 psi (lower than normal pressure gradient).
- No abnormal temperature or pressures are anticipated.
- The formations to be penetrated do not contain known H₂S gas.

CONFIDENTIAL

DRILLING PLAN

APPROVAL OF OPERATIONS

11. WATER SUPPLY

- No water pipelines will be laid for this well.
- No water well will be drilled for this well.
- Drilling water for this will be hauled on the road(s) shown in Attachment No. 3.
- Water will be hauled from: Water Permit # 43-10447 Section 9, Township 8 South, Range 20 East

12. CEMENT SYSTEMS

a. Surface Cement:

- Drill 12-1/4" hole to 2,000'±, run and cement 8-5/8" to surface (depth to vary based on depth of lost circulation zone).
- Pump 20 bbls lightly weighted water spacer followed by 5 bbls fresh water. Displace with any available water.
- Casing to be run with: a) guide shoe b) insert float c) three (3) centralizers, one on each of first 3 joints d) stop ring for plug two joints off bottom e) bottom three joints thread locked f) pump job with bottom plug only.
- Cement the casing annulus to surface. Top out jobs to be performed if needed. Depending to depth of top of cement in the annulus, a 1" tubing string may or may not be utilized.

| <u>Type</u> | <u>Sacks</u> | <u>Interval</u> | <u>Density</u> | <u>Yield</u> | <u>Hole</u> <u>Volume</u> | <u>Cement</u> <u>Volume</u> | <u>Excess</u> |
|-------------|--------------|-----------------|----------------|--------------|------------------------------|--------------------------------|-------------------|
| Lead | 252 | 0'-1,500' | 11.0 ppg | 3.82 CFS | 619 CF | 835 CF | 35% |
| Tail | 219 | 1,500'-2,000' | 15.6 ppg | 1.18 CFS | 220 CF | 297 CF | 35% |
| Top Out | 100 | 0'-200' | 15.6 ppg | 1.18 CFS | 95 CF | 118 CF | 24% (if required) |

Lead Mix: Premium Plus V blend. Blend includes Class "G" cement, gel, salt, gilsonite.
Slurry yield: 3.82 cf/sack Slurry weight: 11.00 #/gal.
Water requirement: 22.95 gal/sack

Tail Mix: Class "G" Cement, 1/4 lb/sk Cellophane Flakes + 2% bwoc Calcium Chloride + 44.3% fresh water.
Slurry yield: 1.18 cf/sack Slurry weight: 15.60 #/gal.
Water requirement: 5.2 gal/sack

Top Out: Class "G" Cement, 1/4 lb/sk Cellophane Flakes + 2% bwoc Calcium Chloride + 44.3% fresh water.
Slurry yield: 1.18 cf/sack Slurry weight: 15.60 #/gal.
Water requirement: 5.2 gal/sack

c. Production Casing Cement:

- Drill 7-7/8" hole to 9,500'±, run and cement 5 1/2".
- Cement interface is at 4,000', which is typically 500'-1,000' above shallowest pay.
- Pump 20 bbl Mud Clean II unweighted spacer, followed by 20 Bbls fresh H2O spacer.
- Displace with 3% KCL.

| <u>Type</u> | <u>Sacks</u> | <u>Interval</u> | <u>Density</u> | <u>Yield</u> | <u>Hole</u> <u>Volume</u> | <u>Cement</u> <u>Volume</u> | <u>Excess</u> |
|-------------|--------------|-----------------|----------------|--------------|------------------------------|--------------------------------|---------------|
| Lead | 160 | 3,700'-4,700' | 11.5 ppg | 3.12 CFS | 175 CF | 350 CF | 100% |
| Tail | 435 | 4,700'-9,500' | 13.0 ppg | 1.75 CFS | 473 CF | 946 CF | 100% |

Note: A caliper log will be ran to determine cement volume requirements.

Lead Mix: Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7.
Slurry yield: 3.12 cf/sack Slurry weight: 11.60 #/gal.
Water requirement: 17.71 gal/sack
Compressives @ 130°F: 157 psi after 24 hours

Tail Mix: Halliburton HLC blend (Prem Plus V/JB flyash). Blend includes Class "G" cement, KCl, EX-1, Halad 322, & HR-5.
Slurry yield: 1.75 cf/sack Slurry weight: 13.00 #/gal.
Water requirement: 9.09 gal/sack
Compressives @ 165°F: 905 psi after 24 hours

13. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: December 1, 2005
Duration: 14 Days

CONFIDENTIAL

SURFACE USE PLAN

CONDITIONS OF APPROVAL

Attachment for Permit to Drill

Name of Operator: Dominion Exploration & Production
Address: 14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134
Well Location: AP 1-2J
700' FNL & 700' FEL
Section 2-11S-19E
Uintah County, UT

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

The onsite inspection for the referenced well is pending with the Utah Division of Oil, Gas and Mining.

1. Existing Roads:

- a. The proposed well site is located approximately 13.97 miles southwest of Ouray, UT.
- b. Directions to the proposed well site have been attached at the end of Exhibit B.
- c. The use of roads under State and County Road Department maintenance are necessary to access the Alger Pass Area. However, an encroachment permit is not anticipated since no upgrades to the State or County Road system are proposed at this time.
- d. All existing roads will be maintained and kept in good repair during all phases of operation.
- e. Vehicle operators will obey posted speed restrictions and observe safe speeds commensurate with road and weather conditions.
- f. Since no improvements are anticipated to the State, County, Tribal or BLM access roads no topsoil striping will occur.
- g. An off-lease federal Right-of-Way is necessary for the access road or utility corridor since both cross off-lease federal acreage. The Right-of-Way has been applied for and is pending approval at this time.

2. Planned Access Roads:

- a. From the existing Alger Pass area access road a new access is proposed trending west approximately 60' to the proposed well site. The access consists of entirely new disturbance and crosses no significant drainages. A road design plan is not anticipated at this time.
- b. The proposed access road will consist of a 24' travel surface within a 30' disturbed area.
- c. Proposed access will utilize entirely State of Utah lands in which a right-of-way is not anticipated at this time.

- d. A maximum grade of 10% will be maintained throughout the project with no cuts and fills required to access the well.
- e. No turnouts are proposed since the access road is only 60' long and adequate site distance exists in all directions.
- f. No culverts or low water crossings are anticipated. Adequate drainage structures will be incorporated into the road.
- g. No surfacing material will come from state, federal or Indian lands.
- h. No gates or cattle guards are anticipated at this time.
- i. Surface disturbance and vehicular travel will be limited to the approved location access road.
- j. All access roads and surface disturbing activities will conform to the standards outlined in the Bureau of Land Management and Forest Service publication: Surface Operating Standards for Oil and Gas Exploration and Development, (1989).
- k. The operator will be responsible for all maintenance of the access road including drainage structures.

3. Location of Existing Wells:

- a. Exhibit B has a map reflecting these wells within a one mile radius of the proposed well.

4. Location of Production Facilities:

- a. All permanent structures will be painted a flat, non-reflective Desert Brown to match the standard environmental colors. All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded.
- b. Site security guidelines identified in 43 CFR 3163.7-5 and Onshore Oil and Gas Order No. 3 will be adhered to.
- c. A gas meter run will be constructed and located on lease within 500 feet of the wellhead. Meter runs will be housed and/or fenced. All gas production and measurement shall comply with the provisions of 43 CFR 3162.7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.
- d. A tank battery will be constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain the storage capacity of the largest tank. All loading lines and valves will be placed inside the berm surrounding the tank battery. All liquid hydrocarbons production and measurement shall conform to the provisions of 43 CFR 3162.7-3 and Onshore Oil and Gas Order No. 4 and Onshore Oil and Gas Order No. 5 for natural gas production and measurement.

- e. Any necessary pits will be properly fenced to prevent any wildlife and livestock entry.
- f. All access roads will be maintained as necessary to prevent erosion and accommodate year-round traffic. The road will be maintained in a safe useable condition.
- g. The site will require periodic maintenance to ensure that drainages are kept open and free of debris, ice, and snow, and that surfaces are properly treated to reduce erosion, fugitive dust, and impacts to adjacent areas.
- h. A gas pipeline is associated with this application and is being applied for at this time. The proposed gas pipeline corridor will leave the east side of the well site and traverse 28' east to the proposed 6" pipeline corridor that will service the Alger Pass area and tie back into the River Bend Federal Unit.
- i. The gas pipeline will be a 6" or less steel surface line within a 20' wide utility corridor. The use of the proposed well site and access roads will facilitate the staging of the pipeline construction. A new pipeline length of approximately 28' is associated with this well.
- j. Dominion intends on installing the pipeline on the surface by welding many joints into long lengths, dragging the long lengths into position and then completing a final welding pass to join the long lengths together. Dominion intends on connecting the pipeline together utilizing conventional welding technology.

5. Location and Type of Water Supply:

- a. The location and type of water supply has been addressed as number 11 within the previous drilling plan information.

6. Source of Construction Material:

- a. The use of materials will conform to 43 CFR 3610.2-3.
- b. No construction materials will be removed from Ute Tribal, SITLA or BLM lands.
- c. If any gravel is used, it will be obtained from a state approved gravel pit.

7. Methods of Handling Waste Disposal:

- a. All wastes associated with this application will be contained and disposed of utilizing approved facilities.
- b. Drill cuttings will be contained and buried on site.
- c. The reserve pit will be located outboard of the location and along the south side of the pad.
- d. The reserve pit will be constructed so as not to leak, break, or allow any discharge.

- e. The reserve pit will be lined with 12 mil minimum thickness plastic nylon reinforced liner material. The liner will overlay a felt liner pad only if rock is encountered during excavation. The pit liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash, scrap pipe, etc., that could puncture the liner will be disposed of in the pit. Pit walls will be sloped no greater than 2:1. A minimum 2-foot freeboard will be maintained in the pit at all times during the drilling and completion operation.
- f. The reserve pit has been located in cut material. Three sides of the reserve pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. After the reserve pit has dried, all areas not needed for production will be rehabilitated.
- g. No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completion of the well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completion of the well.
- h. Trash will be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations. The contents of the trash container will be hauled off periodically to the approved Uintah County Landfill near Vernal, Utah.
- i. Produced fluids from the well other than water will be produced into a test tank until such time as construction of production facilities is completed. Any spills of oil, gas, salt water or other produced fluids will be cleaned up and removed.
- j. After initial clean-up, a 400 bbl tank will be installed to contain produced waste water. This water will be transported from the tank to an approved Dominion disposal well for disposal.
- k. **Produced water from the production well will be disposed of at the RBU 13-11F or RBU 16-19F disposal wells in accordance with Onshore Order #7.**
- l. Any salts and/or chemicals, which are an integral part of the drilling system, will be disposed of in the same manner as the drilling fluid.
- m. Sanitary facilities will be on site at all times during operations. Sewage will be placed in a portable chemical toilet and the toilet replaced periodically utilizing a licensed contractor to transport by truck the portable chemical toilet so that its contents can be delivered to the Vernal Wastewater Treatment Facility in accordance with state and county regulations.

8. Ancillary Facilities:

- a. Garbage Containers and Portable Toilets are the only ancillary facilities proposed in this application.

9. Well Site Layout: (See Exhibit B)

- a. The well will be properly identified in accordance with state regulations.
- b. Access to the well pad will be from the east.

- c. The pad and road designs are consistent with State and Federal specification
- d. A pre-construction meeting with responsible company representative, contractors, State Representatives and the Utah Division of Oil, Gas and Mining will be conducted at the project site prior to commencement of surface-disturbing activities. The pad and road will be construction-staked prior to this meeting.
- e. The pad has been staked at its maximum size of 355' X 200'; however it will be constructed smaller if possible, depending upon rig availability. Should the layout change, this application will be amended and approved utilizing a sundry notice.
- f. All surface disturbing activities, will be supervised by a qualified, responsible company representative who is aware of the terms and conditions of the APD and specifications in the approved plans.
- g. All cut and fill slopes will be such that stability can be maintained for the life of the activity.
- h. Diversion ditches will be constructed as shown around the well site to prevent surface waters from entering the well site area.
- i. The site surface will be graded to drain away from the pit to avoid pit spillage during large storm events.
- j. The stockpiled topsoil (first 6 inches or maximum available) will be stored in a windrow on the uphill side of the location to prevent any possible contamination. All topsoil will be stockpiled for reclamation in such a way as to prevent soil loss and contamination.
- k. Pits will remain fenced until site cleanup.
- l. The blooie line will be located at least 100 feet from the well head.
- m. Water injection may be implemented if necessary to minimize the amount of fugitive dust.

10. Plans for Restoration of the Surface:

- a. Site reclamation for a producing well will be accomplished for portions of the site not required for the continued operation of the well.
- b. The Operator will control noxious weeds along access road use authorizations, pipeline route authorizations, well sites, or other applicable facilities by spraying or mechanical removal. A list of noxious weeds may be obtained from the Utah Division of Oil, Gas and Mining or the appropriate County Extension Office.
- c. Upon well completion, any hydrocarbons in the pit shall be removed. Once the reserve pit is dry, the plastic nylon reinforced liner shall be torn and perforated before backfilling of the reserve pit. The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours.
- d. The cut and fill slopes and all other disturbed areas not needed for the production operation will be top soiled and re-vegetated. The stockpiled topsoil will be evenly distributed over the disturbed area.
- e. Prior to reseeding the site, all disturbed areas, including the access road, will be scarified and left with a rough surface. The site will then be seeded and/or planted as prescribed by the State. The State recommended seed mix will be detailed within their approval documents.

11. Surface and Mineral Ownership:

- a. Surface Ownership – State of Utah – under the management of the SITLA -State Office, 675 East 500 South, Suite 500, Salt Lake, City, Utah 84102-2818; 801-538-5100.
- b. Mineral Ownership – State of Utah – under the management of the SITLA -State Office, 675 East 500 South, Suite 500, Salt Lake, City, Utah 84102-2818; 801-538-5100.

12. Other Information:

- a. AIA Archaeological has conducted a Class III archeological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by AIA Archaeological.
- b. Alden Hamblin will has conducted a paleontological survey. A copy of the report has been submitted under separate cover to the appropriate agencies by Alden Hamblin.
 - i. **Alden must be notified prior to construction to monitor construction activities at the site since paleontological resources were discovered just off-site.**
- c. **A Federal right-of-way must be in place prior to any disturbance on offset federal lands.**

13. Operator's Representative and Certification

| <u>Title</u> | <u>Name</u> | <u>Office Phone</u> |
|------------------------------------|-----------------|---------------------|
| Company Representative (Roosevelt) | Ken Secrest | 1-435-722-4521 |
| Company Representative (Oklahoma) | Carla Christian | 1-405-749-5263 |
| Agent for Dominion | Don Hamilton | 1-435-719-2018 |

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exists; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Dominion Exploration & Production, Inc. and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided under Dominion's State bond. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Signature: Don Hamilton Date: 8-17-05

ORIGINAL

DOMINION EXPLR. & PROD., INC.

AP #1-2J

SECTION 2, T11S, R19E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 9.1 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 2.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE WEST; TURN RIGHT AND PROCEED IN A WESTERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTH; TURN RIGHT AND PROCEED IN A NORTHERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 2.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 2.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN RIGHT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 2.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN LEFT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 1.2 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN SOUTHERLY DIRECTION APPROXIMATELY 1.8 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE WEST; FOLLOW ROAD FLAGS IN A WESTERLY DIRECTION APPROXIMATELY 60' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 54.8 MILES.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

DOMINION EXPLR. & PROD., INC.

TYPICAL CROSS SECTIONS FOR

AP #1-2J



SECTION 2, T11S, R19E, S.L.B.&M.

700' FNL 700' FEL

1" = 20'
X-Section
Scale
1" = 50'

DATE: 05-31-05

Drawn By: L.K.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE YARDAGES

CUT

(6") Topsoil Stripping = 1,690 Cu. Yds.

Remaining Location = 4,800 Cu. Yds.

TOTAL CUT = 6,490 CU.YDS.

FILL = 2,960 CU.YDS.

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

EXCESS MATERIAL = 3,530 Cu. Yds.

Topsoil & Pit Backfill (1/2 Pit Vol.) = 3,250 Cu. Yds.

EXCESS UNBALANCE (After Rehabilitation) = 280 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

DOMINION EXPLR. & PROD., INC.

AP #1-2J

LOCATED IN UINTAH COUNTY, UTAH
SECTION 2, T11S, R19E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: WESTERLY



UELS

Uintah Engineering & Land Surveying

85 South 200 East Vernal, Utah 84078
435-789-1017 uels@uelsinc.com

LOCATION PHOTOS


05 20 05
MONTH DAY YEAR

PHOTO

TAKEN BY: B.B.

DRAWN BY: C.P.

REVISED: 00-00-00



LEGEND:

○ PROPOSED LOCATION

N

DOMINION EXPLR. & PROD., INC.

AP #1-2J

SECTION 2, T11S, R19E, S.L.B.&M.

700' FNL 700' FEL




Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

TOPOGRAPHIC
MAP

| | | |
|-------|-----|------|
| 05 | 20 | 05 |
| MONTH | DAY | YEAR |

SCALE: 1:100,000 DRAWN BY: C.P. REVISED: 00-00-00





LEGEND:

- EXISTING ROAD
- PROPOSED ACCESS ROAD

DOMINION EXPLR. & PROD., INC.

AP #1-2J

SECTION 2, T11S, R19E, S.L.B.&M.

700' FNL 700' FEL



Uintah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



TOPOGRAPHIC
MAP

05 20 05
 MONTH DAY YEAR


SCALE: 1" = 2000'

DRAWN BY: C.P.

REVISED: 00-00-00

B
 TOPO

C
TOPO



APPROXIMATE TOTAL PIPELINE DISTANCE = 28' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- PROPOSED PIPELINE
- PROPOSED PIPELINE (SERVICING OTHER WELLS)

DOMINION EXPLR. & PROD., INC.

AP #1-2J

SECTION 2, T11S, R19E, S.L.B.&M.

700' FNL 700' FEL



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



**TOPOGRAPHIC
MAP**

05 20 05
MONTH DAY YEAR


SCALE: 1" = 1000' DRAWN BY: C.P. REVISED: 00-00-00

**D
TOPO**

CONFIDENTIAL

LEGEND

O = Oil Line
 G = Gas Line
 W = Water Line
 R = Relief Line (Pressure)
 C = Condensate Line
 V = Vent Line
 D = Drain Line
 M = Gas Meter
 P = Pump
 BP = Back Pressure Valve
 SWS = Sealed When Shipping
 SUS = Sealed Unless Shipping
 T = Heat Traced Line
 H = Heater
 BL = Buried Line
 X = Valve
 / = Check Valve
 SC = Sealed Closed Valve
 NC = Normally Closed
 BD = Blowdown Line




The site security plan is on file in DEPI's district office located at 1400 N. State St., Roosevelt, Utah. It can be inspected during office hours, from 6:30 AM thru 3:30 PM, Monday thru Friday..


DOMINION EXPLORATION & PRODUCTION, INC.

| | | |
|----------|----------------------|--------------|
| 1: | | not to scale |
| FLOW/SEP | TYPICAL FLOW DIAGRAM | date: / / |

BOP STACK



CHOKE MANIFOLD



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 08/22/2005

API NO. ASSIGNED: 43-047-37041

WELL NAME: AP 1-2J

OPERATOR: DOMINION EXPL & PROD (N1095)

CONTACT: DON HAMILTON

PHONE NUMBER: 435-650-1886

PROPOSED LOCATION:

NENE 02 110S 190E

SURFACE: 0700 FNL 0700 FEL

BOTTOM: 0700 FNL 0700 FEL

UINTAH

UNDESIGNATED (2)

LEASE TYPE: 3 - State

LEASE NUMBER: ML-36213

SURFACE OWNER: 3 - State

PROPOSED FORMATION: MVRD

COALBED METHANE WELL? NO

INSPECT LOCATN BY: / /

| Tech Review | Initials | Date |
|-------------|----------|---------|
| Engineering | DLD | 9/14/05 |
| Geology | | |
| Surface | | |

LATITUDE: 39.89445

LONGITUDE: -109.7516

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Fed[] Ind[] Sta[] Fee[]
(No. 76S63050600)
☒ Potash (Y/N)
☒ Oil Shale 190-5 (B) or 190-3 or 190-13
☒ Water Permit
(No. 43-10447)
☒ RDCC Review (Y/N)
(Date:)
☒ Fee Surf Agreement (Y/N)
☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

___ R649-2-3.
Unit ___
☒ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
___ R649-3-3. Exception
___ Drilling Unit
Board Cause No: ___
Eff Date: ___
Siting: ___
___ R649-3-11. Directional Drill

COMMENTS:

Needs Permit (09-02-05)

STIPULATIONS:

1- Spacing Strip
2- STATEMENT OF BASIS
3- Cont Strip #3 - (5 1/2" production, ± 3700' mo)

SQUAWS CROSSING II UNIT

NATURAL BUTTES FIELD

WELL HD 121-34

WELL HD 109-35

T10S R19E

T11S R19E

AP 1-2J

AP 2-2J

AP 1-2J

AP 5-2J

ALGER
PASS 1

AP 8-2J

AP 10-2J

AP 9-2J

AP 15-2J

OPERATOR: DOMINION EXPL & PROD (N1095)

SEC: 2 T. 11S R. 19E

FIELD: UNDESIGNATED (002)

COUNTY: UINTAH

SPACING: R649-3-2 / GENERAL SITING

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Wells Status

- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL
- DRILLING



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 25-AUG-2005

**DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL**

STATEMENT OF BASIS

OPERATOR: _____ DOMINION EXPLORATION & PRODUCTION, INC.
WELL NAME & NUMBER: _____ AP 1-2J
API NUMBER: _____ 43-047-37041
LOCATION: 1/4,1/4 NE/NE Sec: 2 TWP: 11S RNG: 19E 700' FNL 700' FEL

Geology/Ground Water:

Dominion proposes to set 2,000 feet of surface casing cemented to the surface. The base of the moderately saline water is estimated at 4,200 feet. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of section 2. The surface formation at this location is the Uinta Formation. The Uinta Formation is made up of discontinuous sands interbedded with shales and are not expected to produce prolific aquifers. The proposed surface casing should adequately protect any near surface aquifers. The production string cement should be brought up above the base of the moderately saline water to prevent it from mixing with fresher waters up hole.

Reviewer: _____ Brad Hill **Date:** _____ 09-12-2005

Surface:

The pre-drill investigation of the surface was performed on 09/02/2005. This site is on State surface with State minerals. Ed Bonner representing SITLA and Ben Williams, Utah Division of Wildlife Resources, were invited to the presite. Both attended. Mr. Williams of the UDWR stated there were no significant wildlife issues with drilling in this area. He Gave Mr. Bonner a recommended seed mix for revegetating the site. The pre-drill investigation did not reveal any significant issues or situations, which should prohibit drilling of this well

Reviewer: _____ Floyd Bartlett **Date:** _____ 09/06/2005

Conditions of Approval/Application for Permit to Drill:

None.

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: DOMINION EXPLORATION & PRODUCTION, INC.

WELL NAME & NUMBER: AP 1-2J

API NUMBER: 43-047-37041

LEASE: State ML-36213 **FIELD/UNIT:** Undesignated

LOCATION: 1/4, 1/4 NE/NE Sec: 2 TWP: 11S RNG: 19E 700' FNL 700' FEL

LEGAL WELL SITING: 460 F SEC. LINE; 460 F 1/4, 1/4 LINE; 920 F ANOTHER WELL.

GPS COORD (UTM): 606729 X; 4416578 Y **SURFACE OWNER:** S.I.T.L.A.

PARTICIPANTS

Floyd Bartlett (DOGM), Edward Bonner (SITLA), Griz Oleen and Ken Secrist (Dominion), Ben Williams (UDWR), Brandon Bowthorpe (U.E.L.S.), Bill McClure and Randy Jackson, (Dirt Contractors).

REGIONAL/LOCAL SETTING & TOPOGRAPHY

The general area is known as Wild Horse Bench and is located approximately 24 miles southwest of Ouray, Utah. Wild Horse Bench is a large open flat area with somewhat steep and frequent side-draws draining to the west toward the Green River and the northeast toward Willow Creek. The Uintah and Ouray Indian Reservation is to the east. This location is on a flat immediately west of the Alger Pass road. The bench has a fair native desert shrub-grass vegetation cover with open spaces protected by a small brown rock pavement. Surface run-off is light.

SURFACE USE PLAN

CURRENT SURFACE USE: Wildlife and Livestock Grazing, Hunting.

PROPOSED SURFACE DISTURBANCE: Location will be 355' by 270'. Access road will be 60 feet extending from the Alger Pass road.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: AP 1 which is plugged is to the south and 7 Federal and 1 State wells to the north..

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: All production facilities will be on location and added after drilling well. Pipeline will follow access road to a main line, which will be constructed to serve other wells in the area.

SOURCE OF CONSTRUCTION MATERIAL: All construction material will be borrowed from site during construction of location.

ANCILLARY FACILITIES: None will be required.

WILL DRILLING AT THIS LOCATION GENERATE PUBLIC INTEREST OR CONCERNS? (EXPLAIN): Unlikely. Area is isolated. Most activity in general area is oilfield related.

WASTE MANAGEMENT PLAN:

Drilled cuttings will be settled into reserve pit. Liquids from pit will be allowed to evaporate. Formation water will be confined to storage tanks. Commercial contractor will handle sewage facilities, storage and disposal. Trash will be contained in trash baskets and hauled to an approved landfill.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: None.

FLORA/FAUNA: Halogeton, curly mesquite, horsebrush, broom snake weed: Wild horses, pronghorn, coyotes, songbirds, raptors, rodents, rabbits, deer, elk.

SOIL TYPE AND CHARACTERISTICS: Brown sandy loam with small brown rock pavement.

EROSION/SEDIMENTATION/STABILITY: Very little natural erosion. Reserve pit is located in cut.

PALEONTOLOGICAL POTENTIAL: None observed

RESERVE PIT

CHARACTERISTICS: 140' by 100' and eight feet deep.

LINER REQUIREMENTS (Site Ranking Form attached): Although not required by the pit characteristics, a 12 mil liner is proposed by the operator for the reserve pit. Sensitivity level II.

SURFACE RESTORATION/RECLAMATION PLAN

As per surface use agreement.

SURFACE AGREEMENT: SITLA

CULTURAL RESOURCES/ARCHAEOLOGY: An archeologist has inspected the site. A copy of this report has been submitted to the State of Utah.

OTHER OBSERVATIONS/COMMENTS

Mr. Williams from the UDWR stated there were no wildlife issues. This pre-drill investigation was conducted on a warm, sunny day.

ATTACHMENTS

Photos of this site were taken and placed on file.

Floyd Bartlett
DOGM REPRESENTATIVE

09/02/2005 1:00 PM
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

| <u>Site-Specific Factors</u> | <u>Ranking</u> | <u>Site Ranking</u> |
|---|----------------|---------------------|
| Distance to Groundwater (feet) | | |
| >200 | 0 | |
| 100 to 200 | 5 | |
| 75 to 100 | 10 | |
| 25 to 75 | 15 | |
| <25 or recharge area | 20 | |
| Distance to Surf. Water (feet) | | |
| >1000 | 0 | |
| 300 to 1000 | 2 | |
| 200 to 300 | 10 | |
| 100 to 200 | 15 | |
| < 100 | 20 | <u>0</u> |
| Distance to Nearest Municipal Well (feet) | | |
| >5280 | 0 | |
| 1320 to 5280 | 5 | |
| 500 to 1320 | 10 | |
| <500 | 20 | <u>0</u> |
| Distance to Other Wells (feet) | | |
| >1320 | 0 | |
| 300 to 1320 | 10 | |
| <300 | 20 | <u>0</u> |
| Native Soil Type | | |
| Low permeability | 0 | |
| Mod. permeability | 10 | |
| High permeability | 20 | <u>10</u> |
| Fluid Type | | |
| Air/mist | 0 | |
| Fresh Water | 5 | |
| TDS >5000 and <10000 | 10 | |
| TDS >10000 or Oil Base Mud Fluid | 15 | |
| containing significant levels of hazardous constituents | 20 | <u>5</u> |
| Drill Cuttings | | |
| Normal Rock | 0 | |
| Salt or detrimental | 10 | <u>0</u> |
| Annual Precipitation (inches) | | |
| <10 | 0 | |
| 10 to 20 | 5 | |
| >20 | 10 | <u>0</u> |
| Affected Populations | | |
| <10 | 0 | |
| 10 to 30 | 6 | |
| 30 to 50 | 8 | |
| >50 | 10 | <u>0</u> |
| Presence of Nearby Utility Conduits | | |
| Not Present | 0 | |
| Unknown | 10 | |
| Present | 15 | <u>0</u> |

Final Score 15 (Level III)

Sensitivity Level I = 20 or more; total containment is required.
Sensitivity Level II = 15-19; lining is discretionary.
Sensitivity Level III = below 15; no specific lining is required.





09-05 Dominion AP 1-2J

Casing Schematic

Clinter

Surface

Proprietary TOC - Surface

8-5/8"
MW 8.4
Frac 19.3

TOC @
176.

Surface
2000. MD

w/18% washout

BHP

$$(0.52)(8.6)(9500) = 4248$$

Anticipate -2000

Gas

$$(0.12)(9500) = 1140$$

MHSP > 3100

fluid

$$(0.22)(9500) = 2090$$

MHSP = 2150

BoPE - 3000 ✓

Surf Csg - 3930

70% = 2751

Max pressure @ Surf shoe = 2548

Test to 2600# ✓

✓ Adequate DWD 9/14/05

5-1/2"
MW 8.6

Production
9500. MD

4200 3min
4245 Washout

TOC @
5036.

6804 TOC Tail

7170 Mesaverde

Proprietary TOC - 3700'

w/15% washout

TOC 3639' w/6% washout

| | | |
|--------------|--|-----------------------------|
| Well name: | 09-05 Dominion AP 1-2J | |
| Operator: | Dominion Exploration & Production, Inc. | |
| String type: | Surface | Project ID: 43-047-37041 |
| Location: | Uintah County | |

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 103 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 162 ft

Cement top: 176 ft

Burst

Max anticipated surface pressure: 1,760 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 2,000 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 1,750 ft

Completion type is subs
Non-directional string.

Re subsequent strings:

Next setting depth: 9,500 ft
Next mud weight: 8.600 ppg
Next setting BHP: 4,244 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,000 ft
Injection pressure 2,000 psi

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Internal Capacity (ft³) |
|---------|---------------------|-----------|-------------------------|-------|------------|----------------------|---------------------|---------------------|-------------------------|
| 1 | 2000 | 8.625 | 32.00 | J-55 | ST&C | 2000 | 2000 | 7.875 | 127.1 |

| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (Kips) | Tension Strength (Kips) | Tension Design Factor |
|---------|---------------------|-------------------------|------------------------|------------------|----------------------|---------------------|---------------------|-------------------------|-----------------------|
| 1 | 873 | 2530 | 2.899 | 2000 | 3930 | 1.97 | 56 | 372 | 6.64 J |

Prepared Clinton Dworshak
by: Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: September 14, 2005
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2000 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

| | | |
|--------------|--|-----------------------------|
| Well name: | 09-05 Dominion AP 1-2J | |
| Operator: | Dominion Exploration & Production, Inc. | |
| String type: | Production | Project ID: 43-047-37041 |
| Location: | Uintah County | |

Design parameters:
Collapse

Mud weight: 8.600 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 208 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 5,036 ft

Burst

Max anticipated surface pressure: 3,104 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 4,244 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Completion type is subs
Non-directional string.

Tension is based on buoyed weight.

Neutral point: 8,261 ft

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Internal Capacity (ft³) |
|---------|---------------------|-----------|-------------------------|--------|------------|----------------------|---------------------|---------------------|-------------------------|
| 1 | 9500 | 5.5 | 17.00 | Mav-80 | LT&C | 9500 | 9500 | 4.767 | 327.4 |

| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (Kips) | Tension Strength (Kips) | Tension Design Factor |
|---------|---------------------|-------------------------|------------------------|------------------|----------------------|---------------------|---------------------|-------------------------|-----------------------|
| 1 | 4244 | 6290 | 1.482 | 4244 | 7740 | 1.82 | 140 | 273 | 1.94 B |

Prepared Clinton Dworshak
by: Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: September 14, 2005
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9500 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

From: Ed Bonner
To: Whitney, Diana
Date: 9/6/2005 12:46:56 PM
Subject: Well Clearance

The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

Dominion Exploration & Production, Inc

- AP 1-2J
- AP 2-2J
- AP 3-2J
- AP 5-2J
- AP 8-2J
- AP 9-2J
- AP 10-2J
- AP 15-2J

EnCana Oil & Gas (USA) Inc
Middle Mesa State 36-14-29-24

EOG Resources, Inc
East Chapita 6-16
East Chapita 7-16
East Chapita 8-16

The Houston Exploration Company
Rock House 13-36
Asphalt Wash 3-16-11-24
Asphalt Wash 4-16-11-24
Asphalt Wash 7-16-11-24
Asphalt Wash 8-16-11-24
Asphalt Wash 12-16-11-24
Asphalt Wash 14-16-11-24
Gusher 6-2

QEP Uinta Basin, Inc
SC 4ML-16-10-23
SC 5ML-16-10-23
SC 12ML-16-10-23
SC 14ML-16-10-23
RW 01-36BG

XTO Energy Inc
State of Utah 17-8-7-34
State of Utah 17-8-15-14

If you have any questions regarding this matter please give me a call.

CC: Garrison, LaVonne; Hill, Brad; Hunt, Gil



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

September 14, 2005

Dominion Exploration & Production, Inc.
14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134

Re: AP 1-2J Well, 700' FNL, 700' FEL, NE NE, Sec. 2, T. 11 South, R. 19 East,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-37041.

Sincerely,

Gil Hunt
Associate Director

pab
Enclosures

cc: Uintah County Assessor
SITLA

Operator: Dominion Exploration & Production, Inc.
Well Name & Number AP 1-2J
API Number: 43-047-37041
Lease: ML-36213

Location: NE NE **Sec.** 2 **T.** 11 South **R.** 19 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.
7. Cement volume for the 5 1/2" production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to $\pm 3700'$ MD as indicated in the submitted drilling plan.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|--|--|---|
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u> | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML - 36213 |
| 2. NAME OF OPERATOR: Dominion Exploration & Production, Inc. | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 3. ADDRESS OF OPERATOR: 14000 Quail Springs CITY Oklahoma City STATE OK ZIP 73134 | | 7. UNIT or CA AGREEMENT NAME: |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 700' FNL & 700' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 2 11S 19E | | 8. WELL NAME and NUMBER: AP 1-2J |
| PHONE NUMBER: (405) 749-1300 | | 9. API NUMBER: 43-047-37041 |
| | | 10. FIELD AND POOL, OR WILDCAT: Natural Buttes |
| | | COUNTY: Uintah |
| | | STATE: UTAH |

| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | | |
|---|---|---|--|
| TYPE OF SUBMISSION | TYPE OF ACTION | | |
| <input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: <u>Extension of APD</u> |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The state APD for this well expires September 14, 2006. Dominion is hereby requesting a one year extension.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 09-25-06
By: [Signature]

| | |
|--|--|
| NAME (PLEASE PRINT) <u>Carla Christian</u> | TITLE <u>Sr. Regulatory Specialist</u> |
| SIGNATURE <u>[Signature]</u> | DATE <u>8/28/2006</u> |

(This space for State use only)

RECEIVED
AUG 31 2006

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-37041
Well Name: AP 1-2J
Location: Section 2-11S-19E, 700' FNL & 700' FEL
Company Permit Issued to: Dominion Exploration & Production, Inc.
Date Original Permit Issued: 9/14/2005

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☐

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

8/28/2006
Date

Title: Sr. Regulatory Specialist

Representing: Dominion Exploration & Production, Inc.

RECEIVED
AUG 31 2006

DIV. OF OIL, GAS & MINING

CONFIDENTIAL

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: DOMINION EXPL & PROD INC

Well Name: AP 1-2J

Api No: 43-047-37041 Lease Type: STATE

Section 02 Township 11S Range 19E County UINTAH

Drilling Contractor BILL JR'S RIG # 6

SPUDDED:

Date 01/04/07

Time 4:00 AM

How DRY

Drilling will Commence: _____

Reported by PAT WISENER

Telephone # (435) 828-1455

Date 01/04/2007 Signed CHD

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|--|--|---|
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML - 36213 |
| 2. NAME OF OPERATOR: Dominion Exploration & Production, Inc. | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 3. ADDRESS OF OPERATOR: 14000 Quail Springs CITY Oklahoma City STATE OK ZIP 73134 | | 7. UNIT or CA AGREEMENT NAME: |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 700' FNL & 700' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 2 11S 19E | | 8. WELL NAME and NUMBER: AP 1-2J |
| PHONE NUMBER: (405) 749-5237 | | 9. API NUMBER: 43-047-37041 |
| | | 10. FIELD AND POOL, OR WILDCAT: Natural Buttes |
| | | COUNTY: Uintah |
| | | STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | | |
|--|--|---|---|--|
| <input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON | |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE | |
| <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL | |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF | |
| | <input type="checkbox"/> COMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: <u>Change TD</u> | |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Dominion request permission to change TD from 9,500' to 10,000'. See attached new drilling plan.

1-9-07
Rm

| | |
|---|------------------------------------|
| NAME (PLEASE PRINT) <u>Barbara Lester</u> | TITLE <u>Regulatory Specialist</u> |
| SIGNATURE <u>Barbara Lester</u> | DATE <u>1/3/2007</u> |

(This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

(5/2000)

DATE 1/8/07
BY: [Signature]

(See Instructions on Reverse Side)

RECEIVED
JAN 03 2007

DIV. OF OIL, GAS & MINING

DRILLING PLAN**APPROVAL OF OPERATIONS****Attachment for Permit to Drill**

Name of Operator: Dominion Exploration & Production
Address: 14000 Quail Springs Parkway, Suite 600
 Oklahoma City, OK 73134
Well Location: AP 1-2J
 700' FNL & 700' FEL
 Section 2-11S-19E
 Uintah County, UT

1. **GEOLOGIC SURFACE FORMATION** Uintah2. **ESTIMATED DEPTHS OF IMPORTANT GEOLOGIC MARKERS**

| <u>Formation</u> | <u>Depth</u> |
|-------------------|--------------|
| Wasatch Tongue | 3,825' |
| Uteland Limestone | 4,155' |
| Wasatch | 4,295' |
| Chapita Wells | 5,195' |
| Uteland Buttes | 6,325' |
| Mesaverde | 7,170' |

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS**

| <u>Formation</u> | <u>Depth</u> | <u>Type</u> |
|-------------------|--------------|-------------|
| Wasatch Tongue | 3,825' | Oil |
| Uteland Limestone | 4,155' | Oil |
| Wasatch | 4,295' | Gas |
| Chapita Wells | 5,195' | Gas |
| Uteland Buttes | 6,325' | Gas |
| Mesaverde | 7,170' | Gas |

4. **PROPOSED CASING PROGRAM**

All casing used to drill this well will be new casing.

| <u>Type</u> | <u>Size</u> | <u>Weight</u> | <u>Grade</u> | <u>Conn.</u> | <u>Top</u> | <u>Bottom</u> | <u>Hole</u> |
|-------------|-------------|---------------|--------------|--------------|------------|---------------|-------------|
| Surface | 8-5/8" | 32.0 ppf | J-55 | STC | 0' | 2,000' | 12-1/4" |
| Production | 5-1/2" | 17.0 ppf | MAV-80 | LTC | 0' | 10,000' | 7-7/8" |

Note: The drilled depth of the surface hole and the setting depth of the surface casing may vary from 1,700' to 2,000'. Should a lost circulation zone be encountered while drilling, casing will be set approximately 300' below the lost circulation zone. If no lost circulation zone is encountered, casing to be set at 2,000'±.

5. **OPERATOR'S MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL**

Surface hole: No BOPE will be utilized. Air foam mist, rotating head and diverter system will be utilized.

Production hole: Prior to drilling out the surface casing shoe, 3,000 psi or greater BOP equipment will be installed. The pipe rams will be operated at least once per day from surface to total depth. The blind rams will be tested once per day from surface to total depth if operations permit.

RECEIVED

JAN 03 2007

DIV. OF OIL, GAS & MINING

DRILLING PLAN**APPROVAL OF OPERATIONS**

A diagram of the planned BOP equipment for normal drilling operations in this area is attached. As denoted there will be two valves and one check valve on the kill line, two valves on the choke line, and two adjustable chokes on the manifold system. The BOP "stack" will consist of two BOP rams (1 pipe, 1 blind) and one annular type preventer, all rated to a minimum of 3,000 psi working pressure.

The BOP equipment will be pressure tested prior to drilling out surface casing shoe and anytime a new casing string is set. All test pressures will be maintained for fifteen (15) minutes without any significant pressure decrease. Clear water will be circulated into the BOP stack and lines prior to pressure testing. The following test pressures will be used as a minimum for various equipment items.

| | | |
|----|---|-----------|
| 1. | Annular BOP | 1,500 psi |
| 2. | Ram type BOP | 3,000 psi |
| 3. | Kill line valves | 3,000 psi |
| 4. | Choke line valves and choke manifold valves | 3,000 psi |
| 5. | Chokes | 3,000 psi |
| 6. | Casing, casinghead & weld | 1,500 psi |
| 7. | Upper kelly cock and safety valve | 3,000 psi |
| 8. | Dart valve | 3,000 psi |

6. **MUD SYSTEMS**

- An air or an air/mist system may be used to drill to drill the surface hole until water influx becomes too great.
- KCL mud system will be used to drill well.
- The mud system will be monitored manually/visually.

| <u>Depths</u> | <u>Mud Weight (ppg)</u> | <u>Mud System</u> |
|------------------|-------------------------|---|
| 0' - 2,000' | 8.4 | Air foam mist, rotating head and diverter |
| 2,000' - 10,000' | 8.6 | Fresh water/2% KCL/KCL mud system |

7. **BLOOIE LINE**

- An automatic igniter will not be installed on blooie line. The blooie will have a constant ignition source.
- A "target tee" connection will be installed on blooie line for 90° change of directions for abrasion resistance.
- "Target tee" connections will be a minimum of 50' from wellhead.
- The blooie line discharge will be a minimum of 80' from the wellhead.

8. **AUXILIARY EQUIPMENT TO BE USED**

- Kelly cock.
- Full opening valve with drill pipe connection will be kept on floor. Valve will be used when the kelly is not in string.

9. **TESTING, LOGGING, AND CORING PROGRAMS TO BE FOLLOWED**

- A drillstem test in the Wasatch Tongue is possible.
- One electric line wire-log will be run from total depth to surface casing.
- The gamma ray will be left on to record from total depth to surface casing.
- Other log curves (resistivities, porosity, and caliper) will record from total depth to surface casing.
- A dipmeter, percussion cores, or rotary cores may be run over selected intervals.

10. **ANTICIPATED ABNORMAL PRESSURES OR TEMPERATURES EXPECTED**

- Expected BHP 1,500-2,000 psi (lower than normal pressure gradient).
- No abnormal temperature or pressures are anticipated.
- The formations to be penetrated do not contain known H₂S gas.

11. **WATER SUPPLY**

- No water pipelines will be laid for this well.
- No water well will be drilled for this well.
- Drilling water for this will be hauled on the road(s) shown in Attachment No. 3.
- Water will be hauled from: Water Permit # 43-10447 Section 9, Township 8 South, Range 20 East

RECEIVED

JAN 03 2007

DIV. OF OIL, GAS & MINING

DRILLING PLAN**APPROVAL OF OPERATIONS****12. CEMENT SYSTEMS****a. Surface Cement:**

- Drill 12-1/4" hole to 2,000'±, run and cement 8-5/8" to surface (depth to vary based on depth of lost circulation zone).
- Pump 20 bbls lightly weighted water spacer followed by 5 bbls fresh water. Displace with any available water.
- Casing to be run with: a) guide shoe b) insert float c) three (3) centralizers, one on each of first 3 joints d) stop ring for plug one joint off bottom e) bottom three joints thread locked f) pump job with bottom plug only. Casing to be centralized with a total of 8 centralizers.
- Cement the casing annulus to surface. Top out jobs to be performed if needed. Depending to depth of top of cement in the annulus, a 1" tubing string may or may not be utilized.

| Type | Sacks | Interval | Density | Yield | Hole Volume | Cement Volume |
|---------|-------|---------------|----------|----------|----------------|------------------|
| Lead | 219 | 0'-1,500' | 11.0 ppg | 3.82 CFS | 619 CF | 836 CF |
| Tail | 236 | 1,500'-2,000' | 15.6 ppg | 1.18 CFS | 206 CF | 279 CF |
| Top Out | 100 | 0'-200' | 15.6 ppg | 1.18 CFS | 87 CF | 118 CF |

Surface design volumes based on 35% excess of gauge hole.

Lead Mix: Halliburton Premium Plus V blend. Blend includes Class "G" cement, gel, salt, gilsonite.
 Slurry yield: 3.82 cf/sack Slurry weight: 11.00 #/gal.
 Water requirement: 22.95 gal/sack

Tail Mix: Class "G" Cement, 1/4 lb/sk Cellophane Flakes + 2% bwoc Calcium Chloride + 44.3% fresh water.
 Slurry yield: 1.18 cf/sack Slurry weight: 15.60 #/gal.
 Water requirement: 5.2 gal/sack

Top Out: Class "G" Cement, 1/4 lb/sk Cellophane Flakes + 2% bwoc Calcium Chloride + 44.3% fresh water.
 Slurry yield: 1.18 cf/sack Slurry weight: 15.60 #/gal.
 Water requirement: 5.2 gal/sack

c. Production Casing Cement:

- Drill 7-7/8" hole to 10,000'±, run and cement 5 1/2".
- Pump 20 bbl Mud Clean II unweighted spacer, followed by 20 Bbls fresh H2O spacer.
- Displace with 2% KCL.
- Production casing to be centralized with 30 centralizers.

| Type | Sacks | Interval | Density | Yield | Hole Volume | Cement Volume |
|------|-------|----------------|----------|----------|----------------|------------------|
| Lead | 90 | 3,495'-4,295' | 11.5 ppg | 3.12 CFS | 139 CF | 277 CF |
| Tail | 1130 | 4,295'-10,000' | 13.0 ppg | 1.75 CFS | 988 CF | 1977 CF |

Production design volumes are estimates based on 35% excess of gauge hole. Actual volumes will be calculated from caliper log to bring lead cement to 800' above top of Wasatch + 15% excess, and tail cement to top of Wasatch + 15% excess.

Lead Mix: Halliburton Prem Plus V blend. Blend includes Class "C" cement, gel, salt, gilsonite, EX-1 and HR-7.
 Slurry yield: 3.12 cf/sack Slurry weight: 11.60 #/gal.
 Water requirement: 17.71 gal/sack
 Compressives @ 130°F: 157 psi after 24 hours

Tail Mix: Halliburton HLC blend (Prem Plus V/JB flyash). Blend includes Class "G" cement, KCl, EX-1, Halad 322, & HR-5.
 Slurry yield: 1.75 cf/sack Slurry weight: 13.00 #/gal.
 Water requirement: 9.09 gal/sack
 Compressives @ 165°F: 905 psi after 24 hours

13. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS

Starting Date: May 3, 2007
 Duration: 14 Days

RECEIVED**JAN 03 2007**

DIV. OF OIL, GAS & MINING

| | | |
|--------------|--|------------------------------------|
| Well name: | 09-05 Dominion AP 1-2Jrev. | |
| Operator: | Dominion Exploration & Production, Inc. | |
| String type: | Production | Project ID: 43-047-37041 |
| Location: | Uintah County | |

Design parameters:
Collapse

Mud weight: 8.600 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 75 °F
Bottom hole temperature: 215 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 2,001 ft

Burst

Max anticipated surface pressure:

3,268 psi *2248 psi w/o 22" internal grad.*

Internal gradient: 0.120 psi/ft

Calculated BHP 4,468 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)

8 Round LTC: 1.80 (J)

Buttress: 1.60 (J)

Premium: 1.50 (J)

Body yield: 1.50 (B)

Completion type is subs
Non-directional string.

Tension is based on buoyed weight.

Neutral point: 8,696 ft

| Run Seq | Segment Length (ft) | Size (in) | Nominal Weight (lbs/ft) | Grade | End Finish | True Vert Depth (ft) | Measured Depth (ft) | Drift Diameter (in) | Internal Capacity (ft³) |
|---------|---------------------|-------------------------|-------------------------|------------------|----------------------|----------------------|---------------------|-------------------------|-------------------------|
| 1 | 10000 | 5.5 | 17.00 | Mav-80 | LT&C | 10000 | 10000 | 4.767 | 1305.3 |
| Run Seq | Collapse Load (psi) | Collapse Strength (psi) | Collapse Design Factor | Burst Load (psi) | Burst Strength (psi) | Burst Design Factor | Tension Load (Kips) | Tension Strength (Kips) | Tension Design Factor |
| 1 | 4468 | 6290 | 1.408 ✓ | 4468 | 7740 | 1.73 ✓ | 148 | 273 | 1.85 B ✓ |

Prepared by: Dustin K. Doucet
Div of Oil, Gas & Minerals

Phone: 801-538-5281
FAX: 801-359-3940

Date: January 8, 2007
Salt Lake City, Utah

Remarks:


Collapse is based on a vertical depth of 10000 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

09-05 Dominion AP 1-2Jrev.

Casing Schematic



w/15g washout

✓ o.k.

Dan

2/18/07

**Dominion**

14000 Quail Springs Parkway, Suite 600
Oklahoma City, Oklahoma 73134

Fax

To: Dustin Doucet, State of Utah**From:** Barbara Lester**Fax:** 801-359-3940**Phone:** 405-749-5237 **FAX:** 405-749-6690**Phone:** 801-538-5281**Pages:** 5 (including cover sheet)**Re:** AP 1-2J Sundry Approval**Date:** 1/3/2007☒ **Urgent**☐ **For Review**☐ **Please Comment**☐ **Please Reply**☐ **Please Recycle**

• Comments:

Dustin,

Please call with verbal approval as soon as possible. Dominion is requesting to change the TD from 9,500' to 10,000'. New drilling plan is attached. They are moving on the well Friday (1-5-07).

Thank you very much,
Barbara
405-749-5237

RECEIVED**JAN 03 2007****DIV. OF OIL, GAS & MINING**

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: Dominion Exploration & Production, Inc.
Address: 14000 Quail Springs Parkway, Suite 600
city Oklahoma City
state OK zip 73134

Operator Account Number: N 1095

Phone Number: (405) 749-5237

Well 1

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|---|-----------------------|-------------------|-----------|-----|----------------------------------|-----|--------|
| 43-047-37041 | AP 1-2J | | NENE | 2 | 11S | 19E | Uintah |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | Entity Assignment Effective Date | | |
| A | 99999 | 15882 | 1/4/2007 | | 1/18/07 | | |
| Comments: <u>MVRD</u> CONFIDENTIAL | | | | | | | |

Well 2

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|-------------|-----------------------|-------------------|-----------|-----|----------------------------------|-----|--------|
| | | | | | | | |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | Entity Assignment Effective Date | | |
| | | | | | | | |
| Comments: | | | | | | | |

Well 3

| API Number | Well Name | | QQ | Sec | Twp | Rng | County |
|-------------|-----------------------|-------------------|-----------|-----|----------------------------------|-----|--------|
| | | | | | | | |
| Action Code | Current Entity Number | New Entity Number | Spud Date | | Entity Assignment Effective Date | | |
| | | | | | | | |
| Comments: | | | | | | | |

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Barbara Lester

Name (Please Print)

Barbara Lester

Signature

Regulatory Specialist

Title

1/18/2007

Date

(5/2000)

RECEIVED

JAN 18 2007

DIV. OF OIL, GAS & MINING

CONFIDENTIAL

FORM 9


STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

| | | |
|---|--|--|
| SUNDRY NOTICES AND REPORTS ON WELLS <small>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</small> | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML - 36213 |
| | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| | | 7. UNIT or CA AGREEMENT NAME: |
| | | 8. WELL NAME and NUMBER: AP 1-2J |
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 9. API NUMBER: 43-047-37041 |
| 2. NAME OF OPERATOR: Dominion Exploration & Production, Inc. | | 10. FIELD AND POOL, OR WILDCAT: Natural Buttes |
| 3. ADDRESS OF OPERATOR: 14000 Quail Springs CITY Oklahoma City STATE OK ZIP 73134 | | PHONE NUMBER: (405) 749-5237 |
| 4. LOCATION OF WELL | | |
| FOOTAGES AT SURFACE: 700' FNL & 700' FEL | | COUNTY: Uintah |
| QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 2 11S 19E | | STATE: UTAH |

| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | | |
|---|---|---|--|
| TYPE OF SUBMISSION | TYPE OF ACTION | | |
| <input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: <u>Spud well</u> |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

1/4/07 - Spud well. Ran 52 jts 8 5/8", 32#, J-55 ST&C csg set @ 2192. Cement lead w/250 sks Hi-Fill "V". Tailed w/225 sks Class "G" 15.8 ppg, 1.15 yld w/no returns. Tailed w/150 sks Class "G", 15.8 ppg, 1.15 yld w/no returns. Wait 1 1/2 hrs & repeat 5 times w/150 sks Class "G", 15.8 ppg, 1.15 yld w/no returns for a total of 900 sks top off. W/returns las 50 sks. 10 bbls cement to surface & stayed.

| | |
|---|------------------------------------|
| NAME (PLEASE PRINT) <u>Barbara Lester</u> | TITLE <u>Regulatory Specialist</u> |
| SIGNATURE  | DATE <u>1/18/2007</u> |

(This space for State use only)

RECEIVED

JAN 25 2007

DIV. OF OIL, GAS & MINING

FACSIMILE COVER PAGE

To : Utah Division of Oil, Gas & Mining
Sent : 2/7/2007 at 3:27:26 PM
Subject : AP 1-2J

From : g
Pages : 3 (including Cover)

CONFIDENTIAL

43-047-37041
211519e

RECEIVED

FEB 07 2007

DIV. OF OIL, GAS & MINING



WELL CHRONOLOGY REPORT

CONFIDENTIAL
RECEIVED
FEB 07 2007

WELL NAME : AP 1-2J

DISTRICT : WESTERN

COUNTY & STATE : UTAH

WI % : 100.00 AFE # : 0700211

DHC : \$630,560

CWC : \$740,710

EVENT DC : \$1,187,088.25

EVENT CC : \$0.00

FIELD : NATURAL BUTTES 630

UT

API # : 43-047-37041

AFE TOTAL : \$1,371,270

EVENT TC : \$1,187,088.25

Event No: 1

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

CONTRACTOR :

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

FORMATION : WASATCH/MESAVERDE

WELL TOTL COST : \$1,187,088

DIV. OF OIL, GAS & MINING

REPORT DATE: 01/30/07 MD : 9,104 TVD : 9,093 DAYS : 9 MW : 9.1 VISC : 39
DAILY : DC : \$37,465.00 CC : \$0.00 TC : \$37,465.00 CUM : DC : \$682,748.00 CC : \$0.00 TC : \$682,748.00
DAILY DETAILS : DRILLED F/ 9093' KB TO 9104' KB. TOOH FOR BIT TRIP. LD OLD MUD MOTOR & BIT. PU NEW MUD MOTOR & BIT. TIH W/ BHA. CUT & SLIP 16 WRAPS OF DRILL LINE. REPLACE RIG BRAKES. WORK ON #1 MUD PUMP MOTOR.

REPORT DATE: 01/31/07 MD : 9,274 TVD : 9,260 DAYS : 10 MW : 9.1 VISC : 48
DAILY : DC : \$33,950.00 CC : \$0.00 TC : \$33,950.00 CUM : DC : \$716,698.00 CC : \$0.00 TC : \$716,698.00
DAILY DETAILS : TIH TO 5000' KB & CIRCULATE. REPAIR #1 MUD PUMP MOTOR. FINISH TRIPPING IN HOLE TO 9104' KB. DRILLED F/ 9104' KB TO 9115' KB. BOP TEST & DRILL. CIRCULATE & REPAIR #2 MUD PUMP. DRILLED F/ 9115' KB TO 9274' KB.

REPORT DATE: 02/01/07 MD : 9,290 TVD : 9,276 DAYS : 11 MW : 9.7 VISC : 36
DAILY : DC : \$42,826.00 CC : \$0.00 TC : \$42,826.00 CUM : DC : \$759,524.00 CC : \$0.00 TC : \$759,524.00
DAILY DETAILS : DRILLED F/ 9274' KB TO 9290' KB. TOOH FOR BIT TRIP. TIH W/ NEW BIT. BIT STUCK @ 9133' KB. CALLED FOR SURFACE JARS & FREE POINT TRUCK. WORKING PIPE WITH RIG WILL WAITING FOR JARS. RU JARS PIPE MOVING.

REPORT DATE: 02/02/07 MD : 9,516 TVD : 9,502 DAYS : 12 MW : 9.5 VISC : 51
DAILY : DC : \$43,821.91 CC : \$0.00 TC : \$43,821.91 CUM : DC : \$803,345.91 CC : \$0.00 TC : \$803,345.91
DAILY DETAILS : JAR STUCK BIT FREE WITH SURFACE JARS. REAM 6 JTS. DRILLED F/ 9290' KB TO 9464' KB. #1 MUD PUMP MOTOR DIED FOR NO REASON WHEN DRILLING. ALMOST GOT STUCK WITH #2 PUMP ON HOLE BY ITSELF WHEN #1 PUMP DIED. DRILLED F/ 9464' KB TO 9505' KB. WORK ON #2 MUD PUMP. CIRCULATE W/ #1 MUD PUMP. CAN'T TRUST #1 MUD PUMP TO KEEP RUNNING. DRILLED F/ 9508' KB TO 9516' KB. WORK ON #1 & #2 MUD PUMP. CIRCULATE W/ #1 PUMP. NOTE #1 MUD PUMP DOWN 1/2 HR WITH NO PUMPS ON THE HOLE & PIPE IN THE HOLE. CAN'T TRUST #2 PUMP END & #1 MUD PUMP ENGINE!!!

REPORT DATE: 02/03/07 MD : 9,673 TVD : 9,659 DAYS : 13 MW : 9.8 VISC : 36
DAILY : DC : \$34,740.00 CC : \$0.00 TC : \$34,740.00 CUM : DC : \$838,085.91 CC : \$0.00 TC : \$838,085.91
DAILY DETAILS : DRILLED F/ 9516' KB TO 9621' KB W/ ONLY #1 MUD PUMP. #2 MUD PUMP DOWN W/ PUMP PROBLEMS. SERVICE RIG. DRILLED F/ 9621' KB TO 9673' KB. W/ ONLY #1 MUD PUMP. #2 MUD PUMP DOWN W/ PUMP PROBLEMS. #2 PUMP HAS BEEN DOWN FOR 30.5 HRS.

REPORT DATE: 02/04/07 MD : 9,811 TVD : 9,797 DAYS : 14 MW : 9.5 VISC : 35
DAILY : DC : \$35,170.00 CC : \$0.00 TC : \$35,170.00 CUM : DC : \$873,255.91 CC : \$0.00 TC : \$873,255.91
DAILY DETAILS : DRILLED F/ 9673' KB TO 9811' KB. TD @ 9811' KB @ 3:00 P.M. (1500 HRS) 2/3/2007. CIRCULATE & CONDITION MUD TO 10.0# & 38 VIS. PUMP PILL & TOOH. SHORT TRIPS F/ 8866' KB TO 9811' KB & 2100' TO 5000' KB. RU & RUN OPEN HOLE LOGS.

REPORT DATE: 02/05/07 MD : 9,810 TVD : 9,796 DAYS : 15 MW : 9.9 VISC : 39
DAILY : DC : \$42,989.07 CC : \$0.00 TC : \$42,989.07 CUM : DC : \$916,244.98 CC : \$0.00 TC : \$916,244.98
DAILY DETAILS : RUN IN W/ OPEN HOLE LOGS TO 4925' KB. HIT BRIDGE. RD & RELEASE OPEN HOLE LOGGERS. TIH TO 9810' KB. CIRCULATE & CONDITION MUD TO 10.2# 42 VIS MUD. TOOH FOR OPEN HOLE LOGS. RU & RUN OPEN HOLE LOGS. LOGGERS NEW TD 9810' KB.



WELL CHRONOLOGY REPORT

CONFIDENTIAL

WELL NAME : AP 1-2J

DISTRICT : WESTERN

COUNTY & STATE : Uintah

WI % : 100.00 AFE # : 0700211

DHC : \$630,560

EVENT DC : \$1,187,088.25

FIELD : NATURAL BUTTES 630

UT

API # : 43-047-37041

AFE TOTAL : \$1,371,270

EVENT CC : \$0.00

Event No: 1

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

CONTRACTOR :

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

FORMATION : WASATCH/MESAVERDE

WELL TOTL COST: \$1,187,088

REPORT DATE: 02/06/07

MD : 9,810

TVD : 9,796

DAYS : 16

MW : 10.1

VISC : 39

DAILY : DC : \$35,735.00

CC : \$0.00

TC : \$35,735.00

CUM : DC: \$951,979.98

CC : \$0.00

TC : \$951,979.98

DAILY DETAILS : RUN OPEN HOLE LOGS. TIH W/ BHA. CUT & SLIP 20 WRAPS OF DRILL LINE. TIH TO 9810' KB. CIRCULATE. TOOHL PIPE & BHA. RU & RUN CASING. RUN 230 JOINTS & TWO 10' MARKER JOINTS OF 5.50", 17.0#, MAV-80, LTC, NEW CASING TO 9778.97' KB MD, TOP OF FC @ 9733.74' KB, 0600 HRS 2/6/07.

REPORT DATE: 02/07/07

MD : 9,810

TVD : 9,796

DAYS : 17

MW :

VISC :

DAILY : DC : \$235,108.27

CC : \$0.00

TC : \$235,108.27

CUM : DC: \$1,187,088.25

CC : \$0.00

TC : \$1,187,088.25

DAILY DETAILS : RU HALLIBURTON & CEMENT 5.500" CSG W/ 65 SKS OF LEAD CEMENT PREMIUM PLUS V BLEND. ADDITIVES; 16% GEL, .6% EX-1, 3% SALT (BWOC), 1% HR-7, .25# / SK. POLYFLAKE, 10# GILSONITE. WEIGHT (LB/GAL) 11.60, YIELD (CUFT/SK) 3.12, WATER (GAL/SK) 17.83. TAIL CEMENT; 831 SKS OF HLC-TYPE V BLEND. ADDITIVES; 65% CEMENT, 35% POZ, 6% GEL, 3% KCL (BWOW), 1% EX-1, .6% HALAD-322, .2% HR-5. WEIGHT (LB/GAL) 13.00, YIELD (CUFT/SK) 1.75, WATER (GAL/SK) 9.06. DISPLACE W/ 230.84 BBLS 2% KCL. FINISHED CEMENTING @ 1000 HRS 2/6/2007. CLEAN PITS. RIG RELEASED @ 1400 HRS 2/6/07. RIG DOWN RIG.

RECEIVED

FEB 07 2007

DIV. OF OIL, GAS & MINING

FACSIMILE COVER PAGE

To : Utah Division of Oil, Gas & Mining

From : g

Sent : 2/14/2007 at 3:05:00 PM

Pages : 4 (including Cover)

Subject : AP 1-2J

43-047-37041
2 115 19e

RECEIVED

FEB 14 2007

DIV. OF OIL, GAS & MINING



WELL CHRONOLOGY REPORT

WELL NAME : AP 1-2J

DISTRICT : WESTERN

FIELD : NATURAL BUTTES 630

Event No: 1

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

COUNTY & STATE : UTAH

UT

CONTRACTOR :

WI % : 100.00 AFE # : 0700211

API # : 43-047-37041

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

DHC : \$630,560

CWC : \$740,710

AFE TOTAL : \$1,371,270

FORMATION : WASATCH/MESAVERDE

EVENT DC : \$1,187,088.25

EVENT CC : \$418,541.00

EVENT TC : \$1,605,629.25

WELL TOTL COST : \$1,605,629

REPORT DATE: 02/07/07

MD : 9,810

TVD : 9,796

DAYS : 17

MW :

VISC :

DAILY : DC : \$235,108.27

CC : \$0.00

TC : \$235,108.27

CUM : DC : \$1,187,088.25

CC : \$0.00

TC : \$1,187,088.25

DAILY DETAILS: RU HALLIBURTON & CEMENT 5.500' CSG W/ 65 SKS OF LEAD CEMENT PREMIUM PLUS V BLEND. ADDITIVES; 16% GEL, .6% EX-1, 3% SALT (BWOC), 1% HR-7, .25# / SK. POLYFLAKE, 10# GILSONITE. WEIGHT (LB/GAL) 11.60, YIELD (CUFT/SK) 3.12, WATER (GAL/SK) 17.83. TAIL CEMENT; 831 SKS OF HLC-TYPE V BLEND. ADDITIVES; 65% CEMENT, 35% POZ, 6% GEL, 3% KCL (BWOW), 1% EX-1, .6% HALAD-322, .2% HR-5. WEIGHT (LB/GAL) 13.00, YIELD (CUFT/SK) 1.75, WATER (GAL/SK) 9.06. DISPLACE W/ 230.84 BBLs 2% KCL. FINISHED CEMENTING @ 1000 HRS 2/6/2007. CLEAN PITS. RIG RELEASED @ 1400 HRS 2/6/07. RIG DOWN RIG.

REPORT DATE: 02/10/07

MD : 9,810

TVD : 9,796

DAYS : 18

MW :

VISC :

DAILY : DC : \$0.00

CC : \$18,793.00

TC : \$18,793.00

CUM : DC : \$1,187,088.25

CC : \$18,793.00

TC : \$1,205,881.25

DAILY DETAILS: MIRU SCHLUMBERGER WIRE LINE AND ACTION HOT OIL SERVICE. RUN CMT BOND LOG UNDER 1500# PRESSURE FROM W.L. PBTD @ 9722' KB TO 2800' KB, FOUND CMT TOP @ 3050' KB. POOH W/ WIRE LINE, AND PRESSURE TESTED CSG TO 5000 PSI, HELD GOOD. RIH AND PERFORATED STAGE #1, SHUT WELL IN, RDMO WIRE LINE AND HOT OILIER. WAIT ON FRAC DATE.

RECEIVED

FEB 14 2007

DIV. OF OIL, GAS & MINING



WELL CHRONOLOGY REPORT

WELL NAME : AP 1-2J

DISTRICT : WESTERN

FIELD : NATURAL BUTTES 630

Event No: 1

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

COUNTY & STATE : UTAH

UT

CONTRACTOR :

WI % : 100.00 AFE # : 0700211

API # : 43-047-37041

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

DHC : \$630,560

CWC : \$740,710

AFE TOTAL : \$1,371,270

FORMATION : WASATCH/MESAVERDE

EVENT DC : \$1,187,088.25

EVENT CC : \$418,541.00

EVENT TC : \$1,605,629.25

WELL TOTL COST : \$1,605,629

REPORT DATE: 02/13/07

MD : 9,810

TVD : 9,796

DAYS : 19

MW :

VISC :

DAILY : DC : \$0.00

CC : \$57,162.00

TC : \$57,162.00

CUM : DC : \$1,187,088.25

CC : \$75,955.00

TC : \$1,263,043.25

DAILY DETAILS : 02-12-2007 AP 1-2J. MIRU SCHLUMBERGER frac equipment, tested lines to 7000 psi. Held safety meeting with all personnel. Quality control on gel & breaker systems with on-site lab was verified. Fraced interval #1, 9422-26', 9456-69', 9676-82', 2 spf, 49 holes, w/ 54,309# 20/40 PR6000 sand. Pumped frac at an avg rate of 37.7 bpm, using 344.9 mscf of N2 and 699 bbls of fluid. Avg surface treating pressure was 4991 psi w/ sand concentrations stair stepping from 1.0 ppg to 4.0 ppg.

4192 gallons Pad YF120ST/N2 gel.

3537 gallons YF120ST/N2 pumped @ 1.0 ppg sand concentration.

4220 gallons YF120ST/N2 pumped @ 2.0 ppg sand concentration.

4218 gallons YF120ST/N2 pumped @ 3.0 ppg sand concentration.

4028 gallons YF120ST/N2 pumped @ 4.0 ppg sand concentration.

9179 gallons WF110 slick water flush.

Total frac fluid pumped 699 bbls. N2 was cut during flush. RIH and set 8K frac plug @ 9380', perforate interval # 2 @ 9162-76', 9196-9200', 9206-14', 9220-26', 9232-44', 9248-62', 9306-14', 9334-44', 1 spf, 84 holes. Fraced interval #2 w/ 106,317# 20/40 PR6000 sand. Pumped frac at an avg rate of 42.4 bpm, using 549.1 mscf of N2 and 1088 bbls of fluid. Avg surface treating pressure was 4467 psi w/ sand concentrations stair stepping from 1.0 ppg to 5.0 ppg.

7685 gallons Pad YF120ST/N2 gel.

3527 gallons pumped YF120ST/N2 @ 1.0 ppg sand concentration.

4924 gallons pumped YF120ST/N2 @ 2.0 ppg sand concentration.

5638 gallons pumped YF120ST/N2 @ 3.0 ppg sand concentration.

5616 gallons pumped YF120ST/N2 @ 4.0 ppg sand concentration.

5267 gallons pumped YF120ST/N2 @ 5.0 ppg sand concentration.

8957 gallons WF110 slick water flush.

Total frac fluid pumped 1088 bbls. N2 was cut during flush. RIH and set 8K frac plug @ 9150', perforate interval # 3 @ 9042-50', 9062-68', 1 spf, 9070-82', 2 spf, 9085-95', 9107-12', 1 spf, 52 holes. Fraced interval #3 w/ 62,511# 20/40 PR6000 sand. Pumped frac at an avg rate of 27.2 bpm, using 422.8 mscf of N2 and 884 bbls of fluid. Avg surface treating pressure was 4501 psi w/ sand concentrations stair stepping from 1.0 ppg to 4.0 ppg.

6423 gallons Pad YF120ST/N2 gel.

3577 gallons pumped YF120ST/N2 @ 1.0 ppg sand concentration.

4226 gallons pumped YF120ST/N2 @ 2.0 ppg sand concentration.

4919 gallons pumped YF120ST/N2 @ 3.0 ppg sand concentration.

4948 gallons pumped YF120ST/N2 @ 4.0 ppg sand concentration.

8770 gallons WF110 slick water flush.

Total frac fluid pumped 884 bbls. N2 was cut during flush. Shut well in overnight, prep to finish in the morning.

RECEIVED

FEB 14 2007

DIV. OF OIL, GAS & MINING



WELL CHRONOLOGY REPORT

WELL NAME : AP 1-2J

DISTRICT : WESTERN

FIELD : NATURAL BUTTES 630

Event No: 1

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

COUNTY & STATE : UTAH

UT

CONTRACTOR :

WI % : 100.00 AFE # : 0700211

API # : 43-047-37041

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

DHC : \$630,560

CWC : \$740,710

AFE TOTAL : \$1,371,270

FORMATION : WASATCH/MESAVERDE

EVENT DC : \$1,187,088.25

EVENT CC : \$418,541.00

EVENT TC : \$1,605,629.25

WELL TOTL COST : \$1,605,629

REPORT DATE: 02/14/07

MD : 9,810

TVD : 9,796

DAYS : 20

MW :

VISC :

DAILY : DC : \$0.00

CC : \$342,586.00

TC : \$342,586.00

CUM : DC : \$1,187,088.25

CC : \$418,541.00

TC : \$1,605,629.25

DAILY DETAILS : 02-13-2007 AP 1-2J W/ SCHLUMBERGER rigged up, RIH and set frac plug @ 8110', perforate interval #4 @ 7726-50', 1 spf, 7767-74', 7974-82', 2 spf, 57 holes. Fraced interval #4, w/ 86,964# 20/40 Ottawa sand. Pumped frac at an avg rate of 37.7 bpm, using 297.3 mscf of N2 and 705 bbls of fluid. Avg surface treating pressure was 4641 psi w/ sand concentrations stair stepping from 2.0 ppg to 6.0 ppg.

4192 gallons Pad YF120ST/N2 gel.

2847 gallons YF120ST/N2 pumped @ 2.0 ppg sand concentration.

2817 gallons YF120ST/N2 pumped @ 3.0 ppg sand concentration.

2819 gallons YF120ST/N2 pumped @ 4.0 ppg sand concentration.

3518 gallons YF120ST/N2 pumped @ 5.0 ppg sand concentration.

3564 gallons YF120ST/N2 pumped @ 6.0 ppg sand concentration.

7461 gallons WF110 slick water flush.

Total frac fluid pumped 705 bbls. N2 was cut during flush. RIH and set 5K frac plug @ 6350', perforate interval #5 @ 5990-98', 6193-6202', 3 spf, 53 holes. Fraced interval #5 w/ 40,134# 20/40 PR6000 sand. Pumped frac at an avg rate of 33 bpm, using 141 mscf of N2 and 453 bbls of fluid. Avg surface treating pressure was 3170 psi w/ sand concentrations stair stepping from 2.0 ppg to 6.0 ppg.

3499 gallons Pad YF115ST/N2 gel.

2198 gallons pumped YF115ST/N2 @ 2.0 ppg sand concentration.

2834 gallons pumped YF115ST/N2 @ 4.0 ppg sand concentration.

2700 gallons pumped YF115ST/N2 @ 6.0 ppg sand concentration.

5816 gallons WF110 slick water flush.

Total frac fluid pumped 453 bbls. N2 was cut during flush. RIH and set 5K frac plug @ 5900', perforate interval #6 @ 5660-69', 6 spf, 55 holes. Fraced interval #3 w/ 23,253# 20/40 Ottawa sand. Pumped frac at an avg rate of 23.8 bpm, using 139.4 mscf of N2 and 330 bbls of fluid. Avg surface treating pressure was 2787 psi w/ sand concentrations stair stepping from 2.0 ppg to 5.0 ppg.

2797 gallons Pad YF115ST/N2 gel.

1786 gallons pumped YF115ST/N2 @ 2.0 ppg sand concentration.

1764 gallons pumped YF115ST/N2 @ 3.0 ppg sand concentration.

1857 gallons pumped YF115ST/N2 @ 5.0 ppg sand concentration.

4015 gallons WF110/N2 slick water flush.

Total frac fluid pumped 330 bbls. N2 was not cut during flush. Opened well to the pit on a 12/64 choke. Truned well over to production.

RECEIVED

FEB 14 2007

DIV. OF OIL, GAS & MINING

FACSIMILE COVER PAGE

To : Utah Division of Oil, Gas & Mining
Sent : 2/21/2007 at 2:04:38 PM
Subject : AP 1-2J

From : g
Pages : 3 (including Cover)

CONFIDENTIAL

43-047-37041
2 11s 19e

RECEIVED

FEB 21 2007

DIV. OF OIL, GAS & MINING



WELL CHRONOLOGY REPORT

WELL NAME : AP 1-2J

DISTRICT : WESTERN

COUNTY & STATE : UTAH

WI % : 100.00 AFE # : 0700211

DHC : \$630,560

EVENT DC : \$1,187,088.25

FIELD : NATURAL BUTTES 630

UT

API # : 43-047-37041

AFE TOTAL : \$1,371,270

EVENT CC : \$418,541.00

Event No: 1

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

CONTRACTOR :

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

FORMATION : WASATCH/MESAVERDE

WELL TOTL COST : \$1,722,494

REPORT DATE: 02/14/07

MD : 9,810

TVD : 9,796

DAYS : 20

MW :

VISC :

DAILY : DC : \$0.00

CC : \$342,586.00

TC : \$342,586.00

CUM : DC : \$1,187,088.25

CC : \$418,541.00

TC : \$1,605,629.25

DAILY DETAILS : 02-13-2007 AP 1-2J W/ SCHLUMBERGER rigged up, RIH and set frac plug @ 8110', perforate interval #4 @ 7726-50', 1 spf, 7767-74', 7974-82', 2 spf, 57 holes. Fraced interval #4, w/ 86,964# 20/40 Ottawa sand. Pumped frac at an avg rate of 37.7 bpm, using 297.3 mscf of N2 and 705 bbls of fluid. Avg surface treating pressure was 4641 psi w/ sand concentrations stair stepping from 2.0 ppg to 6.0 ppg.

4192 gallons Pad YF120ST/N2 gel.

2847 gallons YF120ST/N2 pumped @ 2.0 ppg sand concentration.

2817 gallons YF120ST/N2 pumped @ 3.0 ppg sand concentration.

2819 gallons YF120ST/N2 pumped @ 4.0 ppg sand concentration.

3518 gallons YF120ST/N2 pumped @ 5.0 ppg sand concentration.

3564 gallons YF120ST/N2 pumped @ 6.0 ppg sand concentration.

7461 gallons WF110 slick water flush.

Total frac fluid pumped 705 bbls. N2 was cut during flush. RIH and set 5K frac plug @ 6350', perforate interval #5 @ 5990-98', 6193-6202', 3 spf, 53 holes. Fraced interval #5 w/ 40,134# 20/40 PR6000 sand. Pumped frac at an avg rate of 33 bpm, using 141 mscf of N2 and 453 bbls of fluid. Avg surface treating pressure was 3170 psi w/ sand concentrations stair stepping from 2.0 ppg to 6.0 ppg.

3499 gallons Pad YF115ST/N2 gel.

2198 gallons pumped YF115ST/N2 @ 2.0 ppg sand concentration.

2834 gallons pumped YF115ST/N2 @ 4.0 ppg sand concentration.

2700 gallons pumped YF115ST/N2 @ 6.0 ppg sand concentration.

5816 gallons WF110 slick water flush.

Total frac fluid pumped 453 bbls. N2 was cut during flush. RIH and set 5K frac plug @ 5900', perforate interval #6 @ 5660-69', 6 spf, 55 holes. Fraced interval #3 w/ 23,253# 20/40 Ottawa sand. Pumped frac at an avg rate of 23.8 bpm, using 139.4 mscf of N2 and 330 bbls of fluid. Avg surface treating pressure was 2787 psi w/ sand concentrations stair stepping from 2.0 ppg to 5.0 ppg.

2797 gallons Pad YF115ST/N2 gel.

1786 gallons pumped YF115ST/N2 @ 2.0 ppg sand concentration.

1764 gallons pumped YF115ST/N2 @ 3.0 ppg sand concentration.

1857 gallons pumped YF115ST/N2 @ 5.0 ppg sand concentration.

4015 gallons WF110/N2 slick water flush.

Total frac fluid pumped 330 bbls. N2 was not cut during flush. Opened well to the pit on a 12/64 choke. Truned well over to production.

REPORT DATE: 02/15/07

MD : 9,810

TVD : 9,796

DAYS : 21

MW :

VISC :

DAILY : DC : \$0.00

CC : \$0.00

TC : \$0.00

CUM : DC : \$1,187,088.25

CC : \$418,541.00

TC : \$1,605,629.25

DAILY DETAILS : OPEN WELL TO PIT ON 12/64 CHOKE @11 :30 AM FCP 2600 PSI TOTAL FLUID PUMPED 4149 BBLS

REPORT DATE: 02/16/07

MD : 9,810

TVD : 9,796

DAYS : 22

MW :

VISC :

DAILY : DC : \$0.00

CC : \$0.00

TC : \$0.00

CUM : DC : \$1,187,088.25

CC : \$418,541.00

TC : \$1,605,629.25

DAILY DETAILS : FLOWING TO PIT ON 12/64 CHOKE FCP 2060 PSI FLOWED BACK 1097 BBLS FLUID CHANGED 18/64 CHOKE

REPORT DATE: 02/17/07

MD : 9,810

TVD : 9,796

DAYS : 23

MW :

VISC :

DAILY : DC : \$0.00

CC : \$0.00

TC : \$0.00

CUM : DC : \$1,187,088.25

CC : \$418,541.00

TC : \$1,605,629.25

DAILY DETAILS : FLOW REPORT WELL TO SALES 15 HRS. MADE 1044 MCF, FCP 1468, SLP 79, 0 OIL, 331 WTR. 18/64 CHOKE LEFT WELL SAME.

RECEIVED
FEB 21 2007

**WELL CHRONOLOGY REPORT****WELL NAME : AP 1-2J**

DISTRICT : WESTERN

FIELD : NATURAL BUTTES 630

Event No: 1

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

COUNTY & STATE : UTAH

UT

CONTRACTOR :

WI % : 100.00 AFE # : 0700211

API # : 43-047-37041

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

DHC : \$630,560

CWC : \$740,710

AFE TOTAL : \$1,371,270

FORMATION : WASATCH/MESAVERDE

EVENT DC: \$1,187,088.25

EVENT CC: \$418,541.00

EVENT TC: \$1,605,629.25

WELL TOTL COST: \$1,722,494

REPORT DATE: 02/18/07

MD : 9,810

TVD : 9,796

DAYS : 24

MW :

VISC :

DAILY : DC : \$0.00

CC : \$0.00

TC : \$0.00

CUM : DC: \$1,187,088.25

CC : \$418,541.00

TC : \$1,605,629.25

DAILY DETAILS : WELL TO SALES 24 HRS MADE 1931 MCF FCP 1327 SLP 84 42 OIL 167 WTR 18/64 CHOKE

RECEIVED**FEB 21 2007**

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
Dominion Exploration & Production, Inc.

3. ADDRESS OF OPERATOR:
14000 Quail Springs CITY Oklahoma City STATE OK ZIP 73134

PHONE NUMBER:
(405) 749-5237

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 700' FNL & 700' FEL

COUNTY: Uintah

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 2 11S 19E

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML - 36213

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
AP 1-2J

9. API NUMBER:
43-047-37041

10. FIELD AND POOL, OR WILDCAT:
Natural Buttes

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|---|---|---|
| <input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: <u>Drilling Operations</u> |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

2/6/07 - Ran 230 jts 5-1/2", 17# MAV-80, L&TC csg set @ 9779'. Cement lead w/65 sks Premium Plus V, 11.6 ppg, 3.12 yld. Tail cement w/831 sks HLC-Type V, 13.0 ppg, 1.75 yld. Clean pits. Rig released.

NAME (PLEASE PRINT) Barbara Lester

TITLE Regulatory Specialist

SIGNATURE

DATE 2/19/2007

(This space for State use only)

RECEIVED

FEB 26 2007

FACSIMILE COVER PAGE

To : Utah Division of Oil, Gas & Mining
Sent : 2/28/2007 at 3:47:02 PM
Subject : AP 1-2J

From : g
Pages : 2 (including Cover)

CONFIDENTIAL

43-047-37041
2 11s 19e

RECEIVED

FEB 28 2007

DIV. OF OIL, GAS & MINING

**WELL CHRONOLOGY REPORT****WELL NAME : AP 1-2J**

Event No: 1

DISTRICT : WESTERN

FIELD : NATURAL BUTTES 630

LOCATION : 700' FNL 700' FEL SEC 2 T 11S R 19E

COUNTY & STATE : UINTAH

UT

CONTRACTOR :

WI % : 100.00 AFE # : 0700211

API # : 43-047-37041

PLAN DEPTH : 9,500

SPUD DATE : 01/04/07

DHC : \$630,560

CWC : \$740,710

AFE TOTAL : \$1,371,270

FORMATION : WASATCH/MESAVERDE

EVENT DC: \$1,187,088.25

EVENT CC: \$418,541.00

EVENT TC: \$1,605,629.25

WELL TOTL COST: \$1,722,494

REPORT DATE: 02/18/07

MD : 9,810

TVD : 9,796

DAYS : 24

MW :

VISC :

DAILY : DC : \$0.00

CC : \$0.00

TC : \$0.00

CUM : DC: \$1,187,088.25

CC : \$418,541.00

TC : \$1,605,629.25

DAILY DETAILS : WELL TO SALES 24 HRS MADE 1931 MCF FCP 1327 SLP 84 42 OIL 167 WTR 18/64 CHOKE

RECEIVED**FEB 28 2007**

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

CONFIDENTIAL

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|--|--|--|
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML - 36213 |
| 2. NAME OF OPERATOR: Dominion Exploration & Production, Inc. | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 3. ADDRESS OF OPERATOR: 14000 Quail Springs CITY Oklahoma City STATE OK ZIP 73134 | | 7. UNIT or CA AGREEMENT NAME: |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 700' FNL & 700' FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE 2 11S 19E | | 8. WELL NAME and NUMBER: AP 1-2J 9. API NUMBER: 43-047-37041 10. FIELD AND POOL, OR WILDCAT: Natural Buttes |
| | | COUNTY: Uintah STATE: UTAH |

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

| TYPE OF SUBMISSION | TYPE OF ACTION | | |
|---|---|---|--|
| <input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input checked="" type="checkbox"/> OTHER: First Sales |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

2/12/07 - Perf & Frac
2/13/07 - Perf & Frac
2/15/07 - First Sales

| | |
|---|-----------------------------|
| NAME (PLEASE PRINT) Barbara Lester | TITLE Regulatory Specialist |
| SIGNATURE  | DATE 3/7/2007 |

(This space for State use only)

RECEIVED

MAR 12 2007

DIV. OF OIL, GAS & MINING

CONFIDENTIAL

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML-36213

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:
AP 1-2J

9. API NUMBER:
43-047-37041

PHONE NUMBER:
(405) 749-1300

10 FIELD AND POOL, OR WILDCAT
Natural Buttes

AT SURFACE: 700' FNL & 700' FEI

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH:

DIV. OF OIL, GAS & MINING

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,
MERIDIAN:

NENE 2 11S 19E

12. COUNTY
 Uintah

13. STATE **UTAH**

15. DATE T.D. REACHED:
2/3/2007

16. DATE COMPLETED: 2/15/2007

ABANDONED ☐ READY TO PRODUCE ☒

17. ELEVATIONS (DF, RKB, RT, GL):
5429' GL

18. TOTAL DEPTH: MD 9,811
TVB

| | | |
|---------------------|-----|-------|
| 19. PLUG BACK T.D.: | MD | 9,722 |
| | TVD | |

20. IF MULTIPLE COMPLETIONS, HOW MANY? *

| | |
|------------------|----|
| 21. DEPTH BRIDGE | MD |
| PLUG SET: | TV |

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

23.

| | | | |
|---------------------|--|------------------------------|-------------------|
| WAS WELL CORED? | NO <input checked="" type="checkbox"/> | YES <input type="checkbox"/> | (Submit analysis) |
| WAS DST RUN? | NO <input checked="" type="checkbox"/> | YES <input type="checkbox"/> | (Submit report) |
| DIRECTIONAL SURVEY? | NO <input checked="" type="checkbox"/> | YES <input type="checkbox"/> | (Submit copy) |

**Platform Express, Compensated Neutron/LithoDensity
High Resolution Laterolog Array, Cmt Bond Log**

24. CASING AND LINER RECORD (Report all strings set in well)

[illegible]

25. TUBING RECORD

[illegible]

26. PRODUCING INTERVALS

| FORMATION NAME | TOP (MD) | BOTTOM (MD) | TOP (TVD) | BOTTOM (TVD) |
|--------------------|----------|-------------|-----------|--------------|
| (A) | | | | |
| (B) See Attachment | | | | |
| (C) | | | | |
| (D) | | | | |

27. PERFORATION RECORD

| INTERVAL (Top/Bot - MD) | SIZE | NO. HOLES | PERFORATION STATUS | |
|-------------------------|------|-----------|-------------------------------|-----------------------------------|
| | | | Open <input type="checkbox"/> | Squeezed <input type="checkbox"/> |
| | | | Open <input type="checkbox"/> | Squeezed <input type="checkbox"/> |
| | | | Open <input type="checkbox"/> | Squeezed <input type="checkbox"/> |
| | | | Open <input type="checkbox"/> | Squeezed <input type="checkbox"/> |

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

| DEPTH INTERVAL | AMOUNT AND TYPE OF MATERIAL |
|----------------|-----------------------------|
| | |
| | See Attachment |
| | |

29. ENCLOSED ATTACHMENTS:

☒ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER:

30. WELL STATUS:

Producing

31. INITIAL PRODUCTION

INTERVAL A (As shown in item #26)

| | | | | | | | | | | | | | | | | | | | | | |
|-----------------------------------|--|------------------------|--|---------------------|--|-----------------------------|--|------------------|--|---------------------------|--|------------------------------|--|--------------------------|--|-------------------|--|--------------------|--|-------------------------------|--|
| DATE FIRST PRODUCED: 2/15/2007 | | TEST DATE: 4/9/2007 | | HOURS TESTED: 24 | | TEST PRODUCTION RATES: → | | OIL – BBL: 18 | | GAS – MCF: 807 | | WATER – BBL: 10 | | PROD. METHOD: Flowing | | | | | | | |
| CHOKE SIZE: 48 | | TGB. PRESS. | | CSG. PRESS. 153 | | API GRAVITY | | BTU – GAS | | GAS/OIL RATIO 1;44,833 | | 24 HR PRODUCTION RATES: → | | OIL – BBL: 18 | | GAS – MCF: 807 | | WATER – BBL: 10 | | INTERVAL STATUS: Producing | |

INTERVAL B (As shown in item #26)

| | | | | | | | | | | |
|----------------------|-------------|-------------|-------------|---------------|---------------|------------------------------|------------|------------|--------------|------------------|
| DATE FIRST PRODUCED: | | TEST DATE: | | HOURS TESTED: | | TEST PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | PROD. METHOD: |
| CHOKE SIZE: | TBG. PRESS. | CSG. PRESS. | API GRAVITY | BTU – GAS | GAS/OIL RATIO | 24 HR PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | INTERVAL STATUS: |

INTERVAL C (As shown in item #26)

| | | | | | | | | | | |
|----------------------|-------------|-------------|-------------|---------------|---------------|------------------------------|------------|------------|--------------|------------------|
| DATE FIRST PRODUCED: | | TEST DATE: | | HOURS TESTED: | | TEST PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | PROD. METHOD: |
| CHOKE SIZE: | TBG. PRESS. | CSG. PRESS. | API GRAVITY | BTU – GAS | GAS/OIL RATIO | 24 HR PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | INTERVAL STATUS: |

INTERVAL D (As shown in item #26)

| | | | | | | | | | | |
|----------------------|-------------|-------------|-------------|---------------|---------------|------------------------------|------------|------------|--------------|------------------|
| DATE FIRST PRODUCED: | | TEST DATE: | | HOURS TESTED: | | TEST PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | PROD. METHOD: |
| CHOKE SIZE: | TBG. PRESS. | CSG. PRESS. | API GRAVITY | BTU – GAS | GAS/OIL RATIO | 24 HR PRODUCTION RATES: → | OIL – BBL: | GAS – MCF: | WATER – BBL: | INTERVAL STATUS: |

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Sold

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

| Formation | Top (MD) | Bottom (MD) | Descriptions, Contents, etc. | Name | Top (Measured Depth) |
|-----------|-------------|----------------|------------------------------|-------------------|-------------------------|
| | | | | Wasatch Tonque | 3,774 |
| | | | | Uteland Limestone | 4,125 |
| | | | | Wasatch | 4,274 |
| | | | | Chapita Wells | 5,127 |
| | | | | Uteland Buttes | 6,230 |
| | | | | Mesaverde | 7,152 |

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Carla Christian

TITLE Supervisor, Regulatory Reports

SIGNATURE

Carla Christian

DATE 4/17/2007

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

AP 1-2J Perforation's & Frac's

Interval #1 Mesaverde 9422 - 26
 9456 – 69
 9676 – 82 49 holes

Frac w/54,309# 20/40 PR6000 sd., w/344.9 mscf of N2 and 699 bbls of YF12OST.

Interval #2 Mesaverde 9162 – 76
 9196 – 00
 9206 – 14
 9220 – 26
 9232 – 44
 9248 – 62
 9306 – 14
 9334 - 44 84 holes

Frac w/106,317# 20/40 PR6000 sd., w/549.1 mscf of N2 and 1088 bbls of YF120ST

Interval #3 Mesaverde 9042 – 50
 9062 – 68
 9070 – 82
 9085 – 95
 9107 - 12 52 holes

Frac w/62,511# 20/40 PR6000 sd., w/422.8 mscf of N2 and 884 bbls of YF120ST

Interval #4 Mesaverde 7726 – 50
 7767 – 74
 7974 – 82 57 holes

Frac w/86,964# 20/40 Ottawa sd., w/297.3 mscf of N2 and 705 bbls of YF120ST

Interval #5 Wasatch 5990 – 98
 6193 – 02 53 holes

Frac w/40,134# 20/40 Ottawa sd., w/141 mscf of N2 and 453 bbls of YF115ST

Interval #6 Wasatch 5660 – 69 55 holes

Frac w/23,253# 20/40 Ottawa sd., w/139.4 mscf of N2 and 330 bbls of YF115ST

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

| |
|--------|
| 1. DJJ |
| 2. CDW |

X - Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

7/1/2007

| | |
|--|--|
| FROM: (Old Operator): N1095-Dominion Exploration & Production, Inc 14000 Quail Springs Parkway, Suite 600 Oklahoma City, OK 73134 Phone: 1 (405) 749-1300 | TO: (New Operator): N2615-XTO Energy Inc 810 Houston St Fort Worth, TX 76102 Phone: 1 (817) 870-2800 |
|--|--|

CA No.

Unit:

| WELL NAME | SEC | TWN | RNG | API NO | ENTITY NO | LEASE TYPE | WELL TYPE | WELL STATUS |
|-------------------|-----|-----|-----|--------|-----------|------------|-----------|-------------|
| SEE ATTACHED LIST | | | | | | | | |

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 8/6/2007
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 8/6/2007
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 8/6/2007
- a. Is the new operator registered in the State of Utah: _____ Business Number: 5655506-0143
- b. If **NO**, the operator was contacted on: _____
- a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA
- Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: _____
- Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: _____
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: _____

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 9/27/2007
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 9/27/2007
- Bond information entered in RBDMS on: 9/27/2007
- Fee/State wells attached to bond in RBDMS on: 9/27/2007
- Injection Projects to new operator in RBDMS on: 9/27/2007
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/27/2007

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: UTB000138
- Indian well(s) covered by Bond Number: n/a
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 104312762
- b. The **FORMER** operator has requested a release of liability from their bond on: 1/23/2008

The Division sent response by letter on: _____

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

| | | |
|---|--|---|
| 1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____ | | 5. LEASE DESIGNATION AND SERIAL NUMBER: |
| 2. NAME OF OPERATOR: XTO Energy Inc. <i>N2615</i> | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 3. ADDRESS OF OPERATOR: 810 Houston Street CITY Fort Worth STATE TX ZIP 76102 | | 7. UNIT or CA AGREEMENT NAME: |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED | | 8. WELL NAME and NUMBER: SEE ATTACHED |
| QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: | | 9. API NUMBER: SEE ATTACHED |
| PHONE NUMBER: (817) 870-2800 | | 10. FIELD AND POOL, OR WILDCAT: Natural Buttes |
| COUNTY: Uintah | | STATE: UTAH |

| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | | |
|--|---|---|--|
| TYPE OF SUBMISSION | TYPE OF ACTION | | |
| <input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____ | <input type="checkbox"/> ACIDIZE | <input type="checkbox"/> DEEPEN | <input type="checkbox"/> REPERFORATE CURRENT FORMATION |
| | <input type="checkbox"/> ALTER CASING | <input type="checkbox"/> FRACTURE TREAT | <input type="checkbox"/> SIDETRACK TO REPAIR WELL |
| | <input type="checkbox"/> CASING REPAIR | <input type="checkbox"/> NEW CONSTRUCTION | <input type="checkbox"/> TEMPORARILY ABANDON |
| | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | <input checked="" type="checkbox"/> OPERATOR CHANGE | <input type="checkbox"/> TUBING REPAIR |
| | <input type="checkbox"/> CHANGE TUBING | <input type="checkbox"/> PLUG AND ABANDON | <input type="checkbox"/> VENT OR FLARE |
| <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____ | <input type="checkbox"/> CHANGE WELL NAME | <input type="checkbox"/> PLUG BACK | <input type="checkbox"/> WATER DISPOSAL |
| | <input type="checkbox"/> CHANGE WELL STATUS | <input type="checkbox"/> PRODUCTION (START/RESUME) | <input type="checkbox"/> WATER SHUT-OFF |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | <input type="checkbox"/> RECLAMATION OF WELL SITE | <input type="checkbox"/> OTHER: _____ |
| | <input type="checkbox"/> CONVERT WELL TYPE | <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION | |

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
Effective July 1, 2007, XTO Energy Inc. has purchased the wells listed on the attachment from:

Dominion Exploration & Production, Inc.
14000 Quail Springs Parkway, Suite 600
Oklahoma City, OK 73134

N1095

James D. Abercrombie
James D. Abercrombie
Sr. Vice President, General Manager - Western Business Unit
(405) 749-1300

Please be advised that XTO Energy Inc. is considered to be the operator on the attached list and is responsible under the terms and conditions of the lease for the operations conducted upon the lease lands. Bond coverage is provided by Nationwide BLM Bond #104312750 and Department of Natural Resources Bond #104312762.

| | |
|---|---|
| NAME (PLEASE PRINT) <i>Edwin S. Ryan, Jr.</i> | TITLE <i>Sr. Vice President - Land Administration</i> |
| SIGNATURE <i>Edwin S. Ryan, Jr.</i> | DATE <i>7/31/2007</i> |

(This space for State use only)

APPROVED *9127107*

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED

AUG 06 2007


DIV. OF OIL, GAS & MINING

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

| api | well_name | qtr_qtr | sec | tpw | rng | lease_num | entity | Lease | well | stat |
|------------|-----------------------------|---------|-----|------|------|----------------|--------|---------|------|------|
| 4301530633 | SKYLINE U 1-6 | NENE | 06 | 160S | 060E | UTU-77263 | 99999 | Federal | GW | DRL |
| 4304731138 | RBU 11-34B | NESW | 34 | 090S | 190E | U-017713 | 7058 | Federal | GW | P |
| 4304731179 | BARTON FED 1-26 | NWSE | 26 | 100S | 190E | U-43156 | 8005 | Federal | GW | P |
| 4304731724 | RBU 11-35B | NESW | 35 | 090S | 190E | U-017713 | 11502 | Federal | GW | S |
| 4304731818 | WILLOW CREEK UNIT 2 | SESW | 05 | 110S | 200E | U-39223 | 11604 | Federal | GW | TA |
| 4304731878 | EVANS FED 3-25 | NENW | 25 | 100S | 190E | U-43156 | 11106 | Federal | GW | P |
| 4304731879 | EVANS FED 41-26 | NENE | 26 | 100S | 190E | U-43156 | 11034 | Federal | GW | P |
| 4304731881 | APACHE 12-25 | NWSW | 25 | 100S | 190E | UTU-3405 | 11080 | Indian | GW | P |
| 4304731897 | END OF THE RAINBOW 21-1 | SWSE | 21 | 110S | 240E | U-54224 | 11223 | Federal | GW | S |
| 4304731922 | APACHE FED 44-25 | SESE | 25 | 100S | 190E | U-3405 | 11185 | Federal | GW | S |
| 4304732094 | RBU 13-35B | SWSW | 35 | 090S | 190E | U-017713 | 7058 | Federal | GW | S |
| 4304732222 | RBU 15-35B | SWSE | 35 | 090S | 190E | U-017713 | 11365 | Federal | GW | S |
| 4304732237 | FEDERAL 13-26B | SWSW | 26 | 090S | 190E | UTU-68625 | 11370 | Federal | GW | S |
| 4304732394 | EVANS FED 12-25A | SWNW | 25 | 100S | 190E | U-43156 | 11451 | Federal | GW | P |
| 4304732395 | EVANS FED 32-26 | SWNE | 26 | 100S | 190E | U-43156 | 11447 | Federal | GW | P |
| 4304732515 | WHB 1-25E | NENE | 25 | 100S | 190E | U-73011 | 11720 | Federal | GW | P |
| 4304732557 | FEDERAL 12-11 | SWNW | 11 | 120S | 240E | UTU-66425 | 11761 | Federal | GW | S |
| 4304732558 | FEDERAL 34-30 | SWSE | 30 | 110S | 230E | UTU-66410 | 11747 | Federal | GW | S |
| 4304732559 | FEDERAL 22-22 | SENW | 22 | 110S | 230E | UTU-66409 | 11746 | Federal | GW | P |
| 4304732560 | FEDERAL 21-27 | NENW | 27 | 100S | 240E | UTU-66422 | 11762 | Federal | GW | P |
| 4304732600 | RBU 1-21EO | NENE | 21 | 100S | 190E | U-013766 | 11783 | Federal | OW | S |
| 4304732681 | LANDING STRIP FEDERAL 44-10 | SESE | 10 | 120S | 240E | UTU-69430 | 11853 | Federal | GW | S |
| 4304733019 | BLACK DRAGON UNIT 31-34 | NWNE | 34 | 100S | 240E | UTU-66422 | 12280 | Federal | GW | P |
| 4304733242 | FEDERAL K 23-22 | NESW | 22 | 110S | 210E | UTU-75098 | 13107 | Federal | GW | P |
| 4304733299 | FED K 12-22 | SWNW | 22 | 110S | 210E | UTU-75098 | 13133 | Federal | GW | P |
| 4304733508 | EVANS FED 15-26E | SWSE | 26 | 100S | 190E | U-3405 | 12767 | Federal | GW | P |
| 4304733509 | EVANS FED 9-26E | NESE | 26 | 100S | 190E | UTU-3405 | 12749 | Federal | GW | P |
| 4304733510 | EVANS FED 10-25E | NWSE | 25 | 100S | 190E | U-3405 | 12927 | Federal | GW | P |
| 4304733511 | EVANS FED 14-25E | SESW | 25 | 100S | 190E | U-3405 | 12793 | Federal | GW | P |
| 4304734000 | RBU 1-18E | NENE | 18 | 100S | 190E | UTU-3576 | 14549 | Federal | GW | P |
| 4304734669 | EVANS FED 4-25E | NENE | 26 | 100S | 190E | U-43156 | 13588 | Federal | GW | P |
| 4304734887 | EVANS FED 2-26E | NWNE | 26 | 100S | 190E | U-43156 | 13830 | Federal | GW | P |
| 4304734908 | EVANS FED 15-25E | NWSE | 25 | 100S | 190E | U-3405 | 14023 | Federal | GW | P |
| 4304734909 | WH FED 11-26E | NESW | 26 | 100S | 190E | UTU-3405 | 14629 | Federal | GW | P |
| 4304734984 | WHB 4-26E | NWNW | 26 | 100S | 190E | U-43156 | 14898 | Federal | GW | P |
| 4304734985 | WHB 6-26E | SENW | 26 | 100S | 190E | U-43156 | 14886 | Federal | GW | P |
| 4304735034 | EVANS FED 8-26E | SENE | 26 | 100S | 190E | U-43156 | 14145 | Federal | GW | P |
| 4304735035 | WHB 12-26E | NWSW | 26 | 100S | 190E | UTU-3405 | 14899 | Federal | GW | P |
| 4304735036 | EVANS FED 11-25E | NESW | 25 | 100S | 190E | UTU-3405 | 14134 | Federal | GW | P |
| 4304735037 | EVANS FED 13-25E | SWSW | 25 | 100S | 190E | UTU-3405 | 14090 | Federal | GW | P |
| 4304735043 | EVANS FED 16-26E | SESE | 26 | 100S | 190E | UTU-3405 | 14372 | Federal | GW | P |
| 4304735063 | EVANS FED 8-25E | SENE | 25 | 100S | 190E | U-43156 | 14089 | Federal | GW | P |
| 4304735064 | EVANS FED 6-25E | SENW | 25 | 100S | 190E | U-43156 | 14135 | Federal | GW | P |
| 4304735065 | EVANS FED 9-25E | NESE | 25 | 100S | 190E | UTU-3405 | 13983 | Federal | GW | P |
| 4304735102 | EVANS FED 2-25E | NWNE | 25 | 100S | 190E | U-43156 | 13956 | Federal | GW | P |
| 4304737451 | WHB 13-26E | SWSW | 26 | 100S | 190E | UTU-3405 | 16058 | Federal | GW | P |
| 4304738869 | LOVE 4-20G | NWNW | 20 | 110S | 210E | UTU-076040 | 16249 | Federal | GW | DRL |
| 4304739064 | UTE TRIBAL 2-11H | NENW | 11 | 110S | 200E | 14-20-H62-5611 | 16072 | Indian | GW | DRL |

N1095 DOMINION E and P, INC. to N2615 XTO ENERGY, INC.

| api | well_name | qtr_qtr | sec | tpw | rng | lease_num | entity | Lease | well | stat |
|------------|---------------------|---------|-----|------|------|------------|--------|-------|------|------|
| 4304731777 | STATE 4-36E | NWNW | 36 | 100S | 190E | ML-42175 | 11186 | State | GW | P |
| 4304731784 | STATE 12-36E | NWSW | 36 | 100S | 190E | ML-42175 | 99998 | State | GW | LA |
| 4304732019 | STATE 11-36E | NESW | 36 | 100S | 190E | ML-42175 | 11232 | State | GW | P |
| 4304732224 | STATE 5-36B | SWNW | 36 | 090S | 190E | ML-45173 | 11363 | State | GW | PA |
| 4304732249 | STATE 9-36B | NESE | 36 | 090S | 190E | ML-45173 | 11372 | State | GW | PA |
| 4304732316 | RBU 12-2F | NWSW | 02 | 100S | 200E | ML-10716 | 99998 | State | GW | LA |
| 4304732404 | STATE 2-36E | NWNE | 36 | 100S | 190E | ML-42175 | 99998 | State | GW | LA |
| 4304732405 | STATE 9-36E | NESE | 36 | 100S | 190E | ML-42175 | 99998 | State | GW | LA |
| 4304732845 | H R STATE S 22-2 | SENE | 02 | 120S | 230E | ML-42215 | | State | GW | LA |
| 4304732870 | H R STATE S 24-2 | SENE | 02 | 120S | 230E | ML-42215 | | State | GW | LA |
| 4304732940 | H R STATE S 42-2 | SENE | 02 | 120S | 230E | ML-42215 | 13175 | State | D | PA |
| 4304732979 | STATE 2-36E | NWNE | 36 | 100S | 190E | ML-42175 | 12390 | State | GW | P |
| 4304733129 | STATE G 22-32 | SENE | 32 | 100S | 230E | ML-47063 | | State | GW | LA |
| 4304733130 | H R STATE S 44-2 | SESE | 02 | 120S | 230E | ML-42215 | | State | GW | LA |
| 4304733169 | STATE M 42-2 | SENE | 02 | 110S | 230E | ML-47078 | | State | GW | LA |
| 4304733173 | STATE M 23-2 | NESW | 02 | 110S | 230E | ML-47078 | | State | GW | LA |
| 4304733174 | STATE M 44-2 | SESE | 02 | 110S | 230E | ML-47078 | | State | GW | LA |
| 4304733175 | STATE N 31-16 | NWNE | 16 | 110S | 240E | ML-47080 | | State | GW | LA |
| 4304733176 | STATE Q 44-16 | SESE | 16 | 120S | 210E | ML-47085 | 13134 | State | D | PA |
| 4304733181 | STATE 1-36E | NENE | 36 | 100S | 190E | ML-42175 | 12539 | State | GW | P |
| 4304733738 | STATE 1-2D | NENE | 02 | 100S | 180E | ML-26968 | | State | GW | LA |
| 4304733740 | STATE 9-2D | NESE | 02 | 100S | 180E | ML-13215-A | | State | GW | LA |
| 4304733837 | STATE 7-36E | SWNE | 36 | 100S | 190E | ML-42175 | 13186 | State | GW | P |
| 4304734012 | CLIFFS 15-21L | SWSE | 21 | 110S | 250E | FEE | | Fee | GW | LA |
| 4304734123 | STATE 15-36E | SWSE | 36 | 100S | 190E | ML-42175 | 13784 | State | GW | P |
| 4304734124 | STATE 9-36E | NESE | 36 | 100S | 190E | ML-42175 | 13760 | State | GW | P |
| 4304734241 | STATE 5-36E | SWNW | 36 | 100S | 190E | ML-42175 | 13753 | State | GW | P |
| 4304734284 | STATE 13-36E | SWSW | 36 | 100S | 190E | ML-42175 | 13785 | State | GW | P |
| 4304734285 | STATE 6-36E | SENE | 36 | 100S | 190E | ML-42175 | 13370 | State | GW | P |
| 4304735089 | WHB 8-36E | SENE | 36 | 100S | 190E | ML-42175 | 14024 | State | GW | P |
| 4304735612 | WHB 14-36E | SENE | 36 | 100S | 190E | ML-42175 | 14759 | State | GW | P |
| 4304736292 | WHB 12-36E | NWSW | 36 | 100S | 190E | ML-42175 | 15116 | State | GW | P |
| 4304736666 | KINGS CANYON 1-32E | NENE | 32 | 100S | 190E | ML-47058 | 14958 | State | GW | P |
| 4304736667 | KINGS CANYON 10-36D | NWSE | 36 | 100S | 180E | ML-047058 | 14959 | State | GW | P |
| 4304737034 | AP 15-2J | SWSE | 02 | 110S | 190E | ML-36213 | 15778 | State | GW | P |
| 4304737035 | AP 10-2J | NWSE | 02 | 110S | 190E | ML-36213 | 16029 | State | GW | S |
| 4304737036 | AP 9-2J | NESE | 02 | 110S | 190E | ML-36213 | 15881 | State | GW | P |
| 4304737037 | AP 8-2J | SENE | 02 | 110S | 190E | ML-36213 | 15821 | State | GW | P |
| 4304737038 | AP 5-2J | SWNW | 02 | 110S | 190E | ML-36213 | 16043 | State | D | PA |
| 4304737039 | AP 3-2J | NENW | 02 | 110S | 190E | ML-36213 | 15910 | State | GW | P |
| 4304737040 | AP 2-2J | NWNE | 02 | 110S | 190E | ML-36213 | 99999 | State | GW | DRL |
| 4304737041 | AP 1-2J | NENE | 02 | 110S | 190E | ML-36213 | 15882 | State | GW | P |
| 4304737659 | KC 8-32E | SENE | 32 | 100S | 190E | ML-047059 | 15842 | State | GW | P |
| 4304737660 | KC 9-36D | SESE | 36 | 100S | 180E | ML-047058 | 99999 | State | GW | DRL |
| 4304738261 | KINGS CYN 2-32E | NWNE | 32 | 100S | 190E | ML-047059 | 15857 | State | GW | DRL |

| | | |
|--|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-36213 |
| 1. TYPE OF WELL Gas Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: XTO ENERGY INC | | 7. UNIT or CA AGREEMENT NAME: |
| 3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410 | | 8. WELL NAME and NUMBER: AP 1-2J |
| PHONE NUMBER: 505 333-3159 Ext | | 9. API NUMBER: 43047370410000 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 0700 FNL 0700 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 02 Township: 11.0S Range: 19.0E Meridian: S | | 9. FIELD and POOL or WILDCAT: ALGER PASS |
| | | COUNTY: UINTAH |
| | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/1/2009 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date: | TYPE OF ACTION <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </div> </div> | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. intends to put this well on pump with the intent of improving production. Please see attached procedure. | | |
| Approved by the Utah Division of Oil, Gas and Mining Date: <u>September 24, 2009</u> By: <u></u> | | |
| NAME (PLEASE PRINT) Barbara Nicol | | PHONE NUMBER 505 333-3642 |
| SIGNATURE N/A | | TITLE Regulatory Clerk |
| | | DATE 9/23/2009 |

ML _____
TJF _____
DLC _____

Algiers Pass 01-02J
Sec 02, T 11 S, R 19 E
Uintah County, Utah
API: 43-047-37041
PWOP AFE# 902899

Surf csg: 8-5/8", 32#, J-55, ST&C csg @ 2,192'. TOC@ surf.

Prod csg: 5-1/2", 17#, MAV-80, LT&C csg @ 9,779'. PBTD (FC) @ 9,733'. TOC @ 3,050'. Cmt'd w/65 sks lead (11.0 ppg, 3.82 cf/sk) & 831 sks 65/35/6 blend tail (13.0 ppg, 1.75 cf/sk yield). Did not circ cmt, TOC @ 3,050' via CBL.

Tbg: 2-3/8", 4.7#, J-55, EUE, 8RD tbg. SN @ 9,645', EOT @ 9,682'.

Perforations: WA: 5,660'-69', 5,990'-98', 6,193'-6,202'.

MV: 7,726'-50', 7,767'-74', 7,974'-82', 9,042'-50', 9,062'-68', 9,070'-82', 9,085'-95', 9,107'-12', 9,162'-76', 9,196'-9,200', 9,206'-14', 9,220'-26', 9,232'-44', 9,248'-62', 9,306'-14', 9,334'-44', 9,422'-26', 9,456'-69', 9,676'-82'.

Recent Prod: Plngr lift, 150 mcf/d, 3.0 BOPD, 2.5 BWPD.

Purpose: Clean out wellbore, DO shoe joint for additional rate hole, and PWOP.

- 1) MIRU PU. MI 9,900' 2-3/8", 4.7#, L-80 tbg. MI 1 -500 bbl tank filled w/KCl substitute water and a flow back tank.
- 2) Blow down and kill well w/KCl substitute water down tubing/casing annulus if necessary. ND WH. NU BOP.
- 3) TIH w/2-3/8" tbg slowly and tag fill (PBTD @ 9,733'). Report fill to Mike Logan. TOH and LD 2-3/8", J-55 tbg.
- 4) TIH w/bit and scraper on 2-3/8", L-80 tbg. CO to top of fish and TOH w/tbg and BHA.
- 5) PU and TIH with STI 4-3/4" overshot with double catch grapple and bumper sub on 2-3/8", L-80 tbg. CO to and retrieve the pump-off sub. TOH and LD BHA and fish.
- 6) TIH w/4-3/4" bit on 2-3/8" tbg. DO FC @ 9,733' and DO shoe joint to 9,770' (New PBTD). TOH and LD BHA.

- 7) TIH with tubing BHA as follows:
 - a) 2-3/8" x 12' pup jt w/1/2" vent hole located 1' from top
 - b) 2-3/8" (1.9" ID) API SN
 - c) 3 jts 2-3/8" tubing
 - d) 5-1/2" TECH TAC (2" ID) @ +/- 9,627'
 - e) 2-3/8" tubing to surface, EOT @ 9,732', SN @ 9,720'
- 8) Swab well until clean fluid is obtained. ND BOP, NU WH.
- 9) TIH with rod BHA as follows:
 - a) 3/4" x 8' - 0.012" Mesh Screen Dip Tube
 - b) 2" x 1-1/4" x 16' x 19' RHBC
 - c) 3/4" x 4' Guided Rod Sub w/mold-on guides
 - d) 3/4" - 21,000 lb HF Shear Tool
 - e) 12 - 1-1/4" API K Sinker Bars
 - f) 36 - 3/4" Norris-96 Rods w/ mold-on guides
 - g) 341 - 3/4" Norris-96 Rods w/T-couplings
 - h) 3/4" x 2' & 3/4" x 4' Norris-96 Spacer Subs
 - i) 1-1/4" x 22' Polished Rod w/liner
- 10) Space out pump with spacer subs. Load tubing and long stroke with rig to ensure pump action. HWO. RDMO PU.
- 11) MI and set a Lufkin RM-320-256-120 pumping unit (min ECB 18,900 lbs) with a C-96 engine. Set CB weights as follows:

| Description | Weight | Position (in) |
|-------------|--------|---------------|
| Left Lag | ORO | 14.0 |
| Left Lead | ORO | 14.0 |
| Right Lag | ORO | 14.0 |
| Right Lead | ORO | 14.0 |

- 12) Gauge tanks. Shoot FL and run dynamometer during pumping unit startup. Start well pumping at 4 SPM and 120" SL for 24 hours. Check fluid level and tank gauges.
- 13) Report pre and post start up data to Mike Logan.

Regulatory:

- Submit subsequent sundry after work has been completed

Pumping Unit

- Lufkin RM-320-256-120 pumping unit
- Arrow C-96 engine
- 9,800' 2-3/8", 4.7#, L-80 tbg

Tubing

- 2-3/8" x 12' pup jt w/1/2" vent hole located 1' from top
- 2-3/8" (1.9" ID) API SN
- 3 jts 2-3/8" tubing
- 5-1/2" TECH TAC (2" ID) @ +/- 9,627'
- 2-3/8" tubing to surface, EOT @ 9,752', SN @ 9,740'

Rods

- 3/4" x 8' – 0.012" Mesh Screen Dip Tube
- 2" x 1-1/4" x 16' x 19' RHBC
- 3/4" x 4' Guided Rod Sub w/mold-on guides
- 3/4" – 21,000 lb HF Shear Tool
- 12 – 1-1/4" API K Sinker Bars
- 36 – 3/4" Norris-96 Rods w/ T-couplings
- 341 – 3/4" Norris-96 Rods w/T-couplings
- 3/4" x 2' & 3/4" x 4' Spacer Subs
- 1-1/4" x 22' Polished Rod w/liner

| | | |
|---|--|--|
| STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING | | FORM 9 |
| SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals. | | 5. LEASE DESIGNATION AND SERIAL NUMBER: ML-36213 |
| 1. TYPE OF WELL Gas Well | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: |
| 2. NAME OF OPERATOR: XTO ENERGY INC | | 7. UNIT or CA AGREEMENT NAME: |
| 3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410 | | 8. WELL NAME and NUMBER: AP 1-2J |
| PHONE NUMBER: 505 333-3159 Ext | | 9. API NUMBER: 43047370410000 |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 0700 FNL 0700 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENE Section: 02 Township: 11.0S Range: 19.0E Meridian: S | | 9. FIELD and POOL or WILDCAT: ALGER PASS |
| | | COUNTY: UINTAH |
| | | STATE: UTAH |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | |
| TYPE OF SUBMISSION | TYPE OF ACTION | |
| <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: | <input type="checkbox"/> ACIDIZE | |
| <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/6/2010 | <input type="checkbox"/> ALTER CASING | |
| <input type="checkbox"/> SPUD REPORT Date of Spud: | <input type="checkbox"/> CHANGE TO PREVIOUS PLANS | |
| <input type="checkbox"/> DRILLING REPORT Report Date: | <input type="checkbox"/> CHANGE TUBING | |
| | <input type="checkbox"/> CHANGE WELL STATUS | |
| | <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS | |
| | <input type="checkbox"/> DEEPEN | |
| | <input type="checkbox"/> FRACTURE TREAT | |
| | <input type="checkbox"/> OPERATOR CHANGE | |
| | <input type="checkbox"/> PLUG AND ABANDON | |
| | <input type="checkbox"/> PRODUCTION START OR RESUME | |
| | <input type="checkbox"/> RECLAMATION OF WELL SITE | |
| | <input type="checkbox"/> REPERFORATE CURRENT FORMATION | |
| | <input type="checkbox"/> SIDETRACK TO REPAIR WELL | |
| | <input type="checkbox"/> TUBING REPAIR | |
| | <input type="checkbox"/> VENT OR FLARE | |
| | <input type="checkbox"/> WATER SHUTOFF | |
| | <input type="checkbox"/> SI TA STATUS EXTENSION | |
| | <input type="checkbox"/> WILDCAT WELL DETERMINATION | |
| | <input checked="" type="checkbox"/> OTHER | |
| | OTHER: CHEM. TREATMENT | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. has performed a chemical treatment on this well per the following: 4/6/2010: MIRU Multi Chem. RU & pump 5 gals 8850 biocide & 4 bbl 2% KCL flush down csg. RDMO Multi Chem. RWTP. Final rpt. | | |
| Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 15, 2010 | | |
| NAME (PLEASE PRINT) Barbara Nicol | PHONE NUMBER 505 333-3642 | TITLE Regulatory Compliance Tech |
| SIGNATURE N/A | DATE 4/14/2010 | |